

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15195-21037-00-00

LEASE NAME Seitz B #2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER _____

SPOT LOCATION SE SW NW

SEC. 33 TWP. 12s RGE. 21w (E) or (W) (W)

COUNTY Trego

Date Well Completed _____

Plugging Commenced 9/21/84

Plugging Completed 9/28/84

LEASE OPERATOR Southern States Oil Co.

ADDRESS P.O. Box 1365, Great Bend, Ks. 67530

PHONE # (316) 792-2585 OPERATORS LICENSE NO. 5354

Character of Well _____
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3899'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	259'	none
				5 1/2"	3894'	2300'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with 5 sacks cement, sand to 3460' & 5 sacks cement. Shot pipe at 2900', 2700', 2500', & 2300'. Pulled 56 joints of pipe. Plugged well with 60 sacks cement, 15 gel, 80 cement with 5 hulls mixed, 10 gel, 8 5/8 plug & 50 sacks 50/50 poz 8% gel.
Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 2nd day of October, 1984



My Commission expires: _____

Irene Hoover
 STATE OF KANSAS, Notary Public

10-04-1984
OCT 04 1984

DRILLER'S LOG

our copy

15-195-21037-00-00

COMPANY: Southern States Oil Company

SEC. 33 T. 12S R. 21W

WELL NAME: Seitz "B" #2

LOC. SE SW NW

COUNTY: Trego

RIG NO. #2

TOTAL DEPTH 3899'

ELEVATION

COMMENCED: 7-5-82

COMPLETED: 7-15-82

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 259' w/175 sx. common, 2% gel, 3% cc.

PRODUCTION: 5 1/2" @ 3894' w/150 sx. common, 10% salt, 10 bbls. SW flush.

LOG

(Figures Indicate Bottom of Formations)

Shale & Sand	262
Shale	1525
Shale & Lime	2425
Lime & Shale	2725
Lime	2915
Lime & Shale	3310
Shale & Lime	3465
Lime	3609
Lime & Shale	3675
Lime	3899
<u>ROTARY TOTAL DEPTH</u>	<u>3899</u>

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1984
08-27-1984
CONSERVATION DIVISION
Wichita, Kansas



STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.
upon oath state that the above and foregoing is a true and correct copy of the log of the
Seitz "B" #2 well.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me this 19 day of July, 1982.

My Appointment Expires:
10-4-83

Juanita M. Green
Juanita M. Green