

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rooks County, Sec. 31 Twp. 10S Rge. 20 ~~W~~ W (W)

Location as "NE/CNWxSWx" or footage from lines E2NE SE

Lease Owner Tenneco Oil Company

Lease Name Arron Thomas Well No. 1-31

Office Address 2000 Classen Building, Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole RT KCC

Date well completed May 11 1970

Application for plugging filed May 11 1970

Application for plugging approved May 11 1970


Plugging commenced May 11 1970

Plugging completed May 11 1970

Reason for abandonment of well or producing formation No Productible Zone

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3840 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	221	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Gunned up pits forming heavy mud, filled hole to 660 feet, pushed wooden plug to 660 feet, cemented with 70 sacks cement, filled hole with heavy mud to 225 feet, pushed wooden plug to 225 feet, cemented with 20 sacks cement. Filled hole to 40 feet, pushed wooden plug to 40 feet, cemented with 10 sacks cement to base of well cellar. Job complete at 11:00 PM 5-11-70.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 20 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company  
Address Box 1164, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.  
Verne A. Morris (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Verne A. Morris

Box 1164, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 70

My commission expires November 5, 1973

Richard Boyd  
Notary Public.


# WELL LOG

COMPANY **Tenneco Oil Company**  
FARM **Aaron Thomas** NO. **1-31**

SEC. **31** T. **10S** R. **20W**  
R<sup>T</sup>K<sup>C</sup>C  
E<sup>Z</sup> NE SE  
LOC.

TOTAL DEPTH **3840'**  
COMM. **5-4-70** COMP. **5-11-70**  
CONTRACTOR **Garvey Drilling Company**

COUNTY **Rooks, Kansas**



CASING  
**8 5/8" @ 221' w/175sx**

ELEVATION  
PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

- 45' Sand & Clay
- 225' Shale
- 390' Shale & Sand
- 1200' Shale w/Sand Streaks
- 1440' Shale & Shell
- 1510' Shale
- 1553' Anhydrite
- 1633' Lime & Shale
- 2055' Shale & Lime
- 2775' Lime & Shale
- 3690' Lime
- 3840' Lime
- 3840' RTD

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 10 1970  
CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas }  
County of Barton } ss

I, Charlene Marker of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Aaron Thomas No. 1-31 well.

Charlene Marker

Subscribed and sworn to before me this 13th day of May 19 70

My Commission Expires: November 5, 1973

Richard Boy  
NOTARY PUBLIC