

4-041711

8-15

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 10-18-51

NE SE NE /4 SEC. 23, 10 S, 20 W  
1650 feet from N section line  
330 feet from E section line

Operator license# 31008 Lease: Rogers 'B' Well # 4

Operator: Paul Bowman Oil Company County: Rooks 123.01

Address: Box 54 Well total depth 3785 feet  
801 Codell Road Conductor Pipe: 0 inch @ 0 feet  
Codell, Kansas 67630-0054 Surface pipe 8 5/8 Inch @ 184 feet  
W/125 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 15 Month: August Year 1995

Plugging proposal received from: Paul Bowman

Company: Bowman Oil Company Phone:

Were: 5 1/2" casing set at 3785' w/125 sxs cement. Perf. At 3783 - 3785'.  
Salt at 2200' - Anhy at 1690' - Dakota at 950' - W.L.M. 3785' - T.O.F. at 1800'.  
Ordered 225 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls with 10 sxs gel.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 31 1995  
8-30-1995

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 6:30 P.M., Day: 15, Month: August, Year: 1995

Actual plugging report: Pumped down 5 1/2" casing - 25 sxs. cement with 200# hulls, followed  
with 10 sxs gel, followed with 175 sxs 60/40 pozmix. Max. P.S.I. 400#. S.I.P. 400#.  
Pumped down 8 5/8" S.P. 50 sxs cement with 150# hulls in cement. Max. P.S.I. 300#.  
S.I.P. 200#.

Remarks: Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING X. Elevation: GL

INVOICED  
DATE 8-31-95  
INV. NO. 43388  
8-15

Dennis L. Hamel  
(agent)

NOV 02 1995