

15-163-00289-00-00  
10-2

27  
R

6-010770

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- 3-14-1951  
NE NW /4 SEC. 23, 10 S, 20 W  
feet from S section line  
feet from E section line

Operator license# 5337 Lease Rogers well # 1

Operator: Nadel & Gussman County Rooks

Address: 3200 1st National Tower Well total depth 3779 feet <sup>122.81</sup>  
Tulsa, OK 74103 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 160 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Nadel & Gussman License# 5337

Address: 3200 1st National Tower - Tulsa, OK 74103

Company to plug at: Hour: P.M. Day: 2 Month: October Year: 91

Plugging proposal received from: Frank Neff

Company: Nadel & Gussman Phone: \_\_\_\_\_

Were: Order 375 sx. cement 60/40 poz. - 8% gel. - 500# hulls.  
Pull 3770' of tubing and rods. 5 1/2" casing @ 3775'. Squeezed  
@ 2900' w/400 sx. and 950' to 1420' w/980 sx. Anhydrite 1650'.  
Dakota 642' - 942'.

Plugging Proposal Received by: Dale F. Balthazor

Plugging operations attended by agent? All  ], Part  ], None  ]

Completed: Hour: 4:30P.M., Day: 2, Month: October, Year: 91

Actual plugging report: Pumped down casing 190 sx. cement w/200#  
hulls. Work pressure 900#. Closed w/400. Pumped down 8 5/8"  
100 sx. cement w/200# hulls. Working pressure 400#. Closed w/200#.

RECEIVED  
KANSAS CORPORATION COMMISSION  
10-10-1991  
OCT 10 1991

Remarks: By: Allied Cement Company

CONSERVATION DIVISION  
WICHITA, KS

**INVOICED**

I did  not  observe the plugging.

*Dale F. Balthazor*

*Adm. S*

DATE 10-30-91  
INV. NO. 33562

(agent)  
Form CP-2/3