

To: **6041168**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-25 15-163-04274-00-01 274R
API NUMBER 15- D - 5676
2-3-56
SW SW SE, SEC. 23, T 10 S, R 20 W/EX
330 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6484
Operator: Anderson Energy Inc.
Name & Address: 200 E. First Street
Suite 414
Wichita, Ks. 67202

Lease Name Page Well # 1
County Rooks 132.60
Well Total Depth 4080 feet
Conductor Pipe: Size 13 3/8 feet 254 cwc 220
Surface Casing: Size 8 5/8 feet 1661' w/760 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well x _____ D&A _____

Other well as hereinafter indicated _____
Allied Cementing Co.

Plugging Contractor _____ License Number _____
Address Russell, Ks.

Company to plug at: Hour: 3:00 PM Day: 24 Month: April Year: 19 90

Plugging proposal received from Steve Robbin

(company name) Express Well Service (phone) _____

were: 4 1/2" casing set at 3900' w/100 sks cement. O.H. 3900' - 4080 and casing

bad at surface; orange peel and below collar leaking. Clean out hole to the bottom of salt formation at 2056'.

Plugging Proposal Received by Herb Deines
Dennis Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 1:30PM Day: 25 Month: April Year: 19 90

ACTUAL PLUGGING REPORT MIRU w/1 1/2" tubing drilled to 2056'; spot 25 sks common w/3/4# f.c. Pull tubing to 1900'. Spot 25 sks common w/1/4# f.c. Pull tubing to 1740'.

Spot 100 sks 65/35 poz 8% gel w/1/4# f.c. Pull tubing to 1400' spot 100 sks 65/35 poz 8% gel w/1/4# f.c. Pull tubing to 700' spot 100 sks 65/35 poz 8% gel w/1/4# f.c. P.O.O.H. w/tubing.

Hook up to 4 1/2" casing, pumped add 300 sks 65/35 poz 8% gel w/1/4# f.c. plus 8 sks hulls mixed in cement. 2:00AM April 25, '90: 9:00 A.M. April 25, '90: W.L.M. to 426' F.o.c.: R.I.H. w/ tubing to 425; circ cement to surface w/25 sks: P.O.O.H. w/tubing. Hooked up to casing and sq to 400# s.i.: Pressured up annulus to 500#. Immediate pressure. Job completed.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
I would like to observe this plugging.

DATE 5-9-90
INV. NO. 28093
5-8-1990

Signed Dennis J. Hamel
(TECHNICIAN)
Dennis Hamel