

4-070080

D-06,120

11-21

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 2-15-57

SE NE NW /4 SEC. 23, 10 S, 20 W  
4290 feet from S section line  
2970 feet from E section line

Operator license# 5337

Lease: Rogers Well # 3

Operator: Nadel & Gussman

County: Rooks 139.98

Address: 15 E.15th - First National Tower  
Suite #3200  
Tulsa, OK 74103

Well total depth 4307 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 210 feet  
W/120 sxs.

ABAND. oil well, Gas well, Input well, SWD. X, D&A

Plugging contractor: Nadel & Gussman License# 5337

Address: 15 W.15th - First National Tower - Suite #3200 - Tulsa, OK 74103

Company to plug at: Hour: 9:00 A.M. Day: 21 Month: November Year: 1997

Plugging proposal received from: Art Rolo

Company: Nadel & Gussman Phone: 785-583-3333

Were: 5 1/2" casing set at 4089' cwc w/1500 sxs. November 28, 1957 - Halliburton Job Ticket #208205K. PBTD 4307' - 218' open hole. Plug according to KCC Rules & Regulations. Ordered 400 sxs 60/40 pozmix - 10% gel with 1/4# flowseal with 1000# hulls.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 11:30 A.M., Day: 21, Month: November, Year: 1997

Actual plugging report: Allied pumped 350 sxs 60/40 pozmix - 10% gel with 1000# hulls. Max. P.S.I. 200#. S.I.P. 200#.

Remarks: Allied short 50 sxs and 1/4# flowseal.

Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC, NO  
Plugged through TUBING, CASING X

Anhy.plug: YES X NO  
Dakota plug: YES X, NO  
Elevation: 2228 GL

I did [ X ] / did not [ ] observe the plugging.

Richard Williams

(agent)

Form CP-2/3

11-26-1997

102

INVOICED

DATE DEC 09 1997

INV. NO. 49613