

15-163-19445-00-01  
8-12

281P

6-041320

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-  
SE NE NE /4 SEC. 23, 10 S, 20 W  
4290 feet from S section line  
330 feet from E section line

Operator license# 30323 Lease Rogers "B" well # 3

Operator: Tex/Con Oil & Gas Co. County Rooks

Address: 9401 SW Freeway Well total depth 3809 feet 123.79  
Houston, Texas 77074 Conductor Pipe: - inch @ - feet  
Surface pipe 8 5/8 Inch @ 218 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#           

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 12 Month: August Year: 91

Plugging proposal received from: Joel Stull

Company: Tex/Con phone:           

Were: 5 1/2" casing set at 3756' w/125 sks. cement. Perfs. at 3768' to 3778'. Perf. anhy. at 1680'. Casing squeezed at 1058' w/150 sks. (1958) Squeezed @ 1141' - 1202' w/130 sx. (1975). Squeezed @ 674' - 706' w/150 sks. (1991). Ordered 350 sks. 65/35 poz. - 8% gel. w/1/4 lb. flocele plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 11:30A.M., Day: 12, Month: August, Year: 91

Actual plugging report: R.I.H. w/tubing to 3000' - Spot 85 sx. cement w/300# hulls in cement. Pull up to 1800'. Spot 130 sx. cement to circ. @ surface. P.O.O.H. w/ tubing. Hooked up to 5 1/2" casing, squeezed 75 sks. cement. Max. 600# P.S.I. S. I. 500# P.S.I. Hooked up to 8 5/8" S.P. Squeezed 35 sks. cement w/150# hulls. Max. 450# P.S.I. S.I. 450# P.S.I.

RECEIVED  
STATE CORPORATION COMMISSION  
8-29-1991  
AUG 29 1991

Remarks: INVOICED

DATE 9-12-91 [  ] did not [  ] observe the plugging.

INV. NO. 33094

*Gib.S.*

Dennis L. Hamel  
(agent)