

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 195-21, 133-0000

NE, Sec. 29, T 12 S, R 21 W
1650 feet from N section line
1040 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5354

Lease Name BLANKLEY Well # A-1

Operator: SOUTHERN STATES OIL CO.
Name & Address P.O. BOX 1365
GREAT BEND, MS.
67530

County TREGO

Well Total Depth 3975 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor SLANSON DRLG. CO License Number 238

Address 200 DOUGLAS BLDG. WICHITA MS. 67202

Company to plug at: Hour: 7:30 PM Day: 19th Month: DEC. Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO RON ROUVE

(company name) SLANSON DRLG. CO. (phone) 316-792-1071

were: 8 5/8" - 269' SP. CUL. w/200' 60/40 FOMIX - 2% GEL - 3% CA-CL. (SUN CNT.)

ORDER - 200' 50/50 FOMIX - 6% GEL - 3% CA-CL. + 8 5/8" PLUG

SPBT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 3870' EI w/20' CNT. -> 2nd PLUG @ 1650' EI w/20' CNT.

3rd PLUG @ 840' EI w/180' CNT. -> 4th PLUG @ 270' EI w/40' CNT.

5th PLUG ^{SOLID BRIDGE} HULL'S PLUG @ 40' EI w/10' CNT. Signed Marion Schmidt
(TECHNICIAN) MSK

10" IN RAT HOLE (CIRCULATE)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:00 PM Day: 19th Month: DEC. Year: 1982

ACTUAL PLUGGING REPORT ORDERED - 200' 50/50 FOMIX 6% GEL - 3% CA-CL. + 8 5/8" PLUG

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

1st PLUG @ 3870' EI w/20' CNT. -> 2nd PLUG @ 1650' EI w/20' CNT.

3rd PLUG @ 840' EI w/180' CNT. -> 4th PLUG @ 270' EI w/40' CNT.

5th PLUG -> ^{SOLID BRIDGE} HULL'S PLUG @ 40' EI w/10' CNT.

10" IN RAT HOLE (CIRCULATE WITH JOINT OF PIPE) (CEMENTED BY SUN CNT.)

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION
01-10-1983
JAN 10 1983

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

NOTICED
2-3-83
2318-W

Signed Marion Schmidt
(TECHNICIAN) MSK