

6 030923

API NUMBER 15- 195-20,912-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW NW, SEC. 33, T 12 S, R 21 W/E
3630 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4678

Lease Name Seitz Well # B 1

Operator: Lasmo Energy Corp.

County Trego 126.95

Name & Address P.O. Box 1365

Well Total Depth 3906 feet

Great Bend, Kansas 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B J Titan License Number _____

Address Hays, Kansas

Company to plug at: Hour: AM Day: 31 Month: 7 Year: 19 87

Plugging proposal received from Buster Humphrey

(company name) Lasmo (phone) _____

were: 8 5/8" set at 309' with 190 sx. 5 1/2" set at 3898 with 150 sx. CIBP

3896 Portcollar at 1464' cmt. Basket at 1506' with 350 sx. Did not circulate. T.O.C.

at 1075' test shows holes above T.O.C. in csg. Order 250 sx. Thriftymix. 65/35 poz

10 % gel. 2% dicel 5 sx. hulls

B.J. Titan Cmt. Co. Sundowner Water Truck

Plugging Proposal Received by Carl Goodrow Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 AM Day: 31 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT Squeeze down back side 100 sx cmt. blend with 1/4 sx hulls

Max. PSI 500# close in 300 #

Squeeze down 5 1/2" csg w/ 150 sx cmt. blend w/4 sx hulls mixed in. Max. PSI 1200 #

close in 500 # plug complete.

STATE CORPORATION COMMISSION

AUG 18 1987

8-18-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did ~~not~~) observe this plugging.

DATE 8-18-87

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

aj INV. NO. 17861