

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03229-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 31-10S-20W
990 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: TRICO WEST Well Number: 203
County: ROOKS Total Vertical Depth: 3694 feet

Operator License No.: 5030
Operator Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 240 175 SX CMT
Production: Size 5.5 feet: 3697 175 SX CMT
Liner: Size feet:

11/20

120.06

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/20/2000 10:00 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 13 sxs gel - 500# hulls.
D.V. at 1585' w/600 sxs.
Casing squeezed at 2674' w/250 sxs.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/20/2000 12:00 PM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing 3630'. Spotted 125 sxs cement with 500# hulls, followed with 13 sxs gel.
Pulled tubing to 1500'.
Spotted and circulated cement to surface with 120 sxs cement.
P.O.O.H. with tubing and filled casing with 10 sxs cement.
8 5/8" S.P. - cement visible at surface.

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 22 2000
CONSERVATION DIVISION
WICHITA, KS

Remarks: LEASE FORMERLY KNOWN AS SCHNEIDER #3.

Plugged through: TBG

District: 04

Signed Dennis J. Hamel
(TECHNICIAN)

100

INVOICED
DATE 12/27/00
NO. 2001061198

Form CP-2/3

DEC 12 2000

CITIES SERVICE

#3 SCHNEIDER

31-10-20W

NW SW SW

Contr. LOHMANN & JOHNSON

ROOKS

County

E 2118 Comm. Comp. 11-25-55 IP 300 BOPD

Tops	Depth	Datum
HEEB	3353	-1235
DODGE	3376	-1258
LANS	3393	-1275
B/KC	3620	-1502
CONG	3616	-1528
ARB	3696	-1578
TD	3698	-1580

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Casing

8" 240

5" 3697

DST 3545-77 1/2 HR, 5' MUD

BHP 0#

DST 3578-3607 1/2 HR, 4'

MUD, BHP 800#

CO 3698: DD 3701

2700' OIH/15 HR: ACID

500: PMP 21 BOPH/4 HR

WHITE SW

+	+	+
+	+	+
+	+	+