

8-29

6 031161

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-23,013-0000  
NE NE NE, SEC. 31, T 10 S, R 20 W/E

4950 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8449

Lease Name Keller Well # 1

Operator: McNames and Patterson  
Name & Address Box 20058  
Wichita, Ks. 67208

County Rooks 120.58

Well Total Depth 3710 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well Gas Well Input Well SWD Well U&A X

Other well as hereinafter indicated

Plugging Contractor Shields Drilling Co. Inc. License Number 5655

Address Russell, Ks.

Company to plug at: Hour: Day: 29 Month: August Year: 19 88

Plugging proposal received from Burton Berry

(company name) Shields Drilling (phone)

were: Order 200 sks 60/40 Poz 6% Gel 3% C.C. 8 5/8" wiper plug. Allied Cement Co.

Use no less than 36 vis mud to circ. Balance and space plugs with no loss or gain of fluid.

RECEIVED

STATE CORPORATION COMMISSION  
10-21-88  
OCT 21 1988

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations Abandoned by Agent?: All Part None X

Operations Hour: 4:30PM Day: 29 Month: August Year: 19 88

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe at 1550' w/25 sks

750' w/100 sks and Hulls

260' w/40 sks

40' w/10 sks wiper plug

15 sks in rathole

10 sks in mousehole.

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 10-25-88

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow

INV. NO. 22701