

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02215-00-00  
Spot: CSESWSE Sec/Twnshp/Rge: 31-10S-20W  
330 feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: THOMAS AARON Well Number: 3  
County: ROOKS <sup>RT</sup> KCC Total Vertical Depth: 3657 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

Production Casing Size: 5.5 feet: 3651 **8/118.85**  
Surface Casing Size: 8.625 feet: 315

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/04/2003 9:00 AM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 10% gel - 1000# hulls.  
Drilled out of the casing at 1078'.  
Junk in the hole.  
80 bbls chempac in annulus.  
Emergency plug with rig over the hole.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/07/2003 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

04-04-2003:  
TIH with tubing to 1046'.  
Mixed and pumped 200 sxs cement with 600# hulls.  
POOH and pumped 200 sxs cement with 400# hulls.  
04-07-2003:  
Filled up 5 1/2" with 25 sxs cement.  
Hooked up to 8 5/8".  
Max. P.S.I. 1000#. S.I.P. 850#.


RECEIVED  
APR 10 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-10-03

INV. NO. 2003061406

APR 08 2003

MAGNOLIA PETROLEUM #3 AARON THOMAS 31-10-20W  
SE SW SE

Contr. \_\_\_\_\_ ROOKS County

E 2051 RB Comm. 3-10-57 Comp. 4-12-57 IP 80 BOPD

Tops	Depth	Datum
HEEB	3292	-1241
TOR	3315	-1264
KC	3330	-1279
SIMP	3636	-1585
ARB	3650	-1599
TD	3657	-1606

Casing


9" 315  
5" 3651

DST 3478-3518/1 HR, 6' SL O SPKD MUD,  
BHP 0#

DST 3522-3541/1 HR, 60' O & GCM, BHP 800#  
DST 3534-46/1 HR, 35' CL O, 25' GSY CCM  
BHP 940#

CO 3655: BAIL 4 GO, NW/1 HR: ACID 1500  
DD 3657: ACID 1000: BAIL 1 B0/1 HR: ACID  
1250: SWB 23 B0 & 2 BW/10 HRS

TRICO POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS