

15-065-00314-0000

90


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

### WELL PLUGGING RECORD

Graham County, Sec. 4 Twp. 10S Rge. 21 000X (W)

Location as "NE/CNW%SW%" or footage from lines NE NE SW  
Lease Owner Okmar Oil Company  
Lease Name Abiram Well No. 1  
Office Address 820 Union National Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed June 22 19 50  
Application for plugging filed May 25 19 61  
Application for plugging approved June 2 19 61  
Plugging commenced June 11 19 61  
Plugging completed June 16 19 61  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production March 16 19 61  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Arbuckle Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3873 Feet  
Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3872'	812'
				8-5/8"	138'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

- 6-11-61 Cleaning out cellar and took unit loose.
- 6-12-61 Helped move pumping unit and rigging up.
- 6-13-61 Ran 5 sacks of cement from 3876' to 3846' had braden head cut off, working 8' tension in 5 1/2" pipe, shot at 3252'.
- 6-14-61 Spotted oil at 3252'.
- 6-16-61 Working 8' tension in 5 1/2", shot at 2500', 2006', 1012', 904', 810', and started 5 1/2" pumped 30 sacks of gel mud at 500' and 20 sacks of cement and 20 sacks of cement at 170' and run 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 12 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.  
Address P. O. Box 114, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Robert M. Beren (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

820 Union National Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of July, 19 61

My commission expires November 16, 1961

[Signature]  
Wanona Duff  
Notary Public.



15-065-00314-0000

ABIRAM WELL # 1

Location:	NE/4 NE/4 SW/4 Sec.4-10S-21W Graham County, Kansas	Date Spudded:	6-11-50
Operator:	Heathman Drilling Co., Inc.	Date Completed:	6-22-50
Contractor:	Heathman Drilling Co., Inc.	Elevation:	2302KB 2300DF
Surface Casing:	4 jts. (138.50') 8-5/8" cemented @ 134 1/2' w/100 sacks and 1 Cal.Chloride.	Total Depth:	3873'
Oil String:	13 1/4 jts. (3876.33') 1 1/2" # 8rd.thd. 5 1/2" cemented @ 3872 (1' off bottom) w/100 sacks cement.		

T O P S KB

Anhydrite	1769 (+ 533)
Topeka	3296 (- 994)
Heebner	3500 (-1198)
Lansing-K.C.	3539 (-1237)
Base K.C.	3764 (-1462)
Marmaton Chert	3818 (-1516)
Simpson	3854 (-1552)
Arbuckle	3870 (-1568)
Total Depth	3873

L O G

(Figures indicate bottom of formation)

Sand and shale	0 to 65
Sand and shale	136
Shale	730
Sand shale	1186
Shale and sand	1275
Sand	1505
Shale and Redbed	1707
Shale	1769
Anhydrite	1811
Shale and shells	2150
Shale and lime	2980
Shale	3218
Shale - lime	3311
Lime	3495
Lime and shale	3625
Lime	3840
Chert - shale	3873
Total Depth	3873'

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 26 1951  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, Robert F. Walters of the Heathman Drilling Co., Inc., hereby certifies that the above is a true and correct log of the formations encountered in drilling the ABIRAM No. 1 well as shown on the daily drilling reports.

*Robert F. Walters*  
\_\_\_\_\_  
Robert F. Walters

Subscribed and sworn before me  
this 27th day of June 1950.

*[Signature]*  
\_\_\_\_\_  
Notary Public

My commission expires: June 23, 1952