


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 4 Twp. 10 Rge. 21 (E) W (W)  
Location as "NE/CNW&SW" or footage from lines. NE/4 NE/4 SW/4  
Lease Owner Okmar Oil Company  
Lease Name Abiram Well No. 3  
Office Address 820 Union National Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 2-26-19 52  
Application for plugging filed 8-7-19 61  
Application for plugging approved 8-8-19 61  
Plugging commenced 1:15 P.M. 8-11-19 61  
Plugging completed 4:15 P.M. 8-11-19 61  
Reason for abandonment of well or producing formation oil depleted

If a producing well is abandoned, date of last production November 19 53  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Kansas City Depth to top Bottom Total Depth of Well 3872 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle		0	166	8 5/8	166	0
		0	3871	5 1/2	3871	319

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

8/10/61 Cleaning out cellar and rigging up

8/11/61 Set plug at 3600' and run 5 sacks of cement shot at 605' and 320' pumped 20 sacks of gel mud and 20 sacks of cement at 320' pumped 20 sacks of mud at 170' and run 10 sacks to base of collar.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 11 1962 06-11-62

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.  
Address 204 E. 6th, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Robert M. Beren (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

820 Union National Bldg, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 8th day of June, 19 62

My commission expires March 12, 1966

Jeannine ReQua  
Jeannine ReQua

Notary Public.



ABIRAM WELL NO. 3 (Twin Well)

Location: NE NE SW Sec. 4-10S-21W Date Spudded: 2-14-52  
Graham County, Kansas

Operator: Okmar Oil Company Rotary Completion: 2-26-52

Contractor: Walters Drilling Co., Inc. Elevation: 2298' Gr; 2300' DF  
2302' KB

Surface Casing: 5 jts. 8 5/8" set at 166'  
with 115 sacks cement and  
1 sack Cal. Chloride.

Oil String: 125 jts. 5 1/2" OD 8 Rd Thd  
set at 3871' with 150  
sacks cement.

GEOLOGICAL TOPS (KB)

Anhydrite	1769	(+533)
Topeka	3292	(-990)
Heebner	3497	(-1195)
Lansing-Kansas City	3537	(-1235)
Base of Kansas City	3763	(-1461)
Marmaton Chert	3816	(-1514)
Conglomerate	3847	(-1545)
Simpson	3852	(-1550)
Arbuckle	3869	(-1567)
Rotary Total Depth	3872	(-1570)

L O G

(Figures indicate bottom of formation)

Surface	0 to 166
Sand and shale	793
Shale and sand	910
Sand	1000
Shale and sand	1260
Sand	1506
Shale and shells	1565
Anhydrite	1811
Shale and shells	2165
Shale and lime shells	2325
Shale and shells	2635
Shale and lime	2828
Shale	3274
Shale and lime	3634
Lime	3638
Lime and shale	3832
Cherty lime and shale	3872
Total Depth (Rotary)	3872

RECEIVED  
STATE CORPORATE COMMISSION  
AUG 8 1961  
REGISTRATION DIVISION  
Topeka, Kansas

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO., INC.

By

Robert F. Walters

Subscribed and sworn to before me  
this 29th day of February, 1952.

James Mott  
Notary Public

By Order of the Commission: June 28, 1952