


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 4 Twp. 10 Rge. 21 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Okmar Oil Company
Lease Name Kern Well No. #4
Office Address 820 Union National Bldg. Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4-10-62 19
Plugging completed 4-11-62 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3871 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug back on top of Lane Well plug at 3616' with 10' of sand.
Mixed and ran 4 sacks cement thru dump baler.
Circulated hole with 19 sack gel and spotted 20 sacks cement at 550' pulled 12 jts.
Spotted 20 sacks cement at 160' - pulled 5 jts. Mudded hole to 35' and sat 5' rock bridge.
Mixed and dumped 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
16 1962
CONSERVATION DIVISION
Wichita, Kansas
04-16-62

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 14 day of April, 1962

My commission expires 24 October 1964
Sidney W. Miller Notary Public.



15-065-01699-0000

CERTIFIED DRILLERS LOG

Company: W. L. Hartman
Contractor: H & H Drilling Company
Commenced: 4-16-51
Completed: 4-28-51 (Rotary)
Elevation: 2301 d.f.
Potential:

Lease: Kern #4
Location: 22' South of
NW NW SE
4-10-21W
Graham County

Casing Record:
104' 8-5/8" cem. W/85 sax.
3870' 5-1/2" cem. W/125 sax.

FORMATION	DEPTH	REMARKS
Cellar	0-100	
Shale	100-1766	
Lime	1766-1803	
Shale	1803-2224	
Shale & Lime	2224-2348	
Shale	2348-2385	
Shale & Lime	2385-2550	
Shale	2550-2621	
Shale	2621-2921	
Lime	2921-2980	
Shale	2980-3072	
Shale & Lime	3072-3156	
Lime & Shale	3156-3401	
Lime	3401-3745	
Shale & Lime	3745-3780	
Lime & Shale	3780-3825	
Lime	3825-3861	
Lime Arbuckle	3861-3871	
Total Depth	3871	

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1951
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log, to the best of my knowledge.

W. L. Hartman

STATE OF KANSAS)
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 31st day of May 1951.

Gerard L. Land
Notary Public

MY COMMISSION EXPIRES: May 13, 1953