


15-065-01693-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Location as "NE/CNW/SW" or footage from lines Graham County, Sec. 4 Twp. 10 Rge. 21 (E) (W)
NW NW SE
Lease Owner Okmar Oil Company
Lease Name Kern Well No. #1
Office Address B20 Union National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8-9-62 _____ 19____
Plugging completed 8-10-62 _____ 19____
Reason for abandonment of well or producing formation _____



If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3871' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 3 sacks mud - Pulled 6 joints - pumped 14 sacks of mud - 20 sacks cement.
Pulled rest of pipe 9 joints. Baled hole down to 30' dumped 10 sacks of cement
for top.

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1962
08-14-62

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.A. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of August, 1962

My commission expires 24 October 1964
Sidney D. Miller Notary Public.



CERTIFIED DRILLERS LOG

OKmar O.K. &

Company: H. L. Willis & H & H Drilling Company Lease: Kern #1
 Contractor: H & H Drilling Company Location: NW NW SE 4-10-21W
 Commenced: 7-28-50 Graham County, Kans.
 Completed: 8-17-50 Casing Record:
 Elevation: 2301 D.F. 104' 8-5/8" cem. W/90 sax.
 Potential: Maximum Well 3869' 5-1/2" cem. W/175 sax.

FORMATION	DEPTH		REMARKS
	From	To	
Clay	0	20	
Sand	20	75	
Shale	75	850	
Shale & Sand	850	1330	
Shale	1330	1760	Trip @ 1620
Anhydrite	1760	1802	
Shale & Shell	1802	1945	
Shale & Lime	1945	2475	Trip @ 2195
Lime	2475	2585	
Shale & Lime	2585	2825	Trip @ 2595
Lime	2825	2890	
Lime & Shale	2890	3009	
Shale & Lime	3009	3275	Trip @ 3181
Shale	3275	3365	Circ. @ 3330, 3365
Lime & Shale	3365	3424	Trip 3424 & Circ.
Lime	3424	3455	Circ. @ 3453
Chert	3455	3458	
Shale & Lime	3458	3518	
Lime	3518	3855	Trip @ 3576, Circ. @ 3582, 94, 3700, 25
Shale	3855	3862	Circ. @ 3765 Trip @ 3673
Lime	3862	3865	Circ. @ 3865
Lime	3865	3871	
Total Depth		3871	

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 24 1962
 CONSERVATION DIVISION
 Wichita, Kansas

GEOLOGICAL DATA:

Drill Stem Test #1 3570-3594, open 15 minutes. Strong blow. Recovered 1565' of good oil and 120' oil cut mud. Initial Flow Pressure 470#. Final Flow Pressure 600#. 1150# B.H.P. in 10 minutes, building up at end of test.

Drill Stem Test #2 3685-3725, open 1/2 hour, faint blow 6 minutes, went dead, recovered 7' mud. B.H.S.I.P. 15 minutes 0#.

Drill Stem Test #3 3733-3765, open 1/2 hour, faint blow 6 minutes, recovered 30' mud. B.H.S.I.P. 850# in 15 minutes.

DERRICK FLOOR DATA
 (Corrected 2 feet for rotary bushing)
 Elevation: 2301 D.F.
 2303 R.B.

Tops:	DEPTH
Anhydrite	1758 (driller's top) / 543
Topeka	3290 -989
Heebner	3496 -1195
Lansing	3531 -1230
Base Kansas City	3757 -1456
Marmaton Chert	3811 -1511
Arbuckle	3866 -1565
Rotary Total Depth	3869 -1568

I hereby certify that this is a true and correct copy of the above log, to the best of my knowledge.

STATE OF KANSAS)
 COUNTY OF SEDGWICK)