


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Rooks County. Sec. 34 Twp. 10 Rge. 20 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines SW NW NE
Lease Owner D. G. Hansen
Lease Name Rossman Well No. 1
Office Address Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 26 19 56
Application for plugging filed July 26 19 56
Application for plugging approved July 26 19 56
Plugging commenced July 27 19 56
Plugging completed July 27 19 56
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3725 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	161'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 156'. Set plug. Put in 1/2 sack Hulls and 15 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack Hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.
Address 107 RULE Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
G. F. Galloway
107 Rule Building
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of July, 1956

My commission expires May 20, 1959
Vicky Jacobs
Vicky Jacobs Notary Public.

PLUGGING
FILE SEC 34 T 10 R 20 W
BOOK PAGE 85 LINE 18

RECEIVED
STATE CORPORATION COMMISSION

07-31-56

CONTRACTOR'S WELL LOG

OPERATOR D. G. HANSEN WELL NAME ROSSMAN #1

LOCATION SW NW NE SECTION 34-10-20W RIG NO. 1

COUNTY ROOKS STATE KANSAS

COMMENCEMENT DATE JULY 17, 1956 COMPLETION DATE JULY 26, 1956

LOG OF WELL

Elevation 2114' rotary bushing.
 All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	161	Shale		
161	970	Shale-Sand		
970	1546	Red Bed		
1546	1585	Anhydrite		
1585	1990	Shale-Shells		
1990	2170	Lime-Shale		
2170	2345	Lime-Shale		
2345	2495	Lime-Shale		
2495	2610	Lime-Shale	0° - 2500	
2610	2825	Lime-Shale	0° - 2750	
2825	2950	Lime-Shale		
2950	3055	Lime-Shale	0° - 3000	
3055	3190	Lime-Shale		
3190	3275	Lime-Shale	0° - 3250	
3275	3330	Lime-Shale		
3330	3435	Lime-Shale		
3435	3480	Lime-Shale		
3480	3510	Lime-Shale	0° - 3500	
3510	3560	Lime-Shale		
3560	3605	Lime-Shale		
3605	3700	Lime-Shale		
3700	3725	Lime-Shale		DST 3705-10

CASING LEFT IN HOLE AFTER COMPLETION

Set 161' of 8-5/8" OD Surface Casing.

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G Drilling Co.
 By G. F. Galloway
 G. F. Galloway

Subscribed and sworn to before me this 28th day of July, 1956.

My commission expires:
 May 20, 1959

Vicky Jacobs
 Vicky Jacobs, Notary Public

PLUGGING
 FILE SEC. 34 T. 10 R. 20W
 BOOK PAGE 85 LINE 18