


15-163-00951-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rooks County. Sec. 34 Twp. 10 Rge. 20 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SE NE NW  
Lease Owner C & G Drilling Co.  
Lease Name Briggs Well No. 12  
Office Address Box 637, Plainville, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed May 20 19 56  
Application for plugging filed October 23 19 61  
Application for plugging approved October 23 19 61  
Plugging commenced October 23 19 61  
Plugging completed October 27 19 61  
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production October 18 19 61  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Elden Petty, Hays  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3712 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	186	None
				5 1/2	3712	2705

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Run bailer to 3475 top bridge plug dumped sand to 3490  
Run bailer to bottom, dumped 5 sacks cement  
Shot pipe at 2705'  
pulled pipe to 500' Cir w/mud mixed 20 sacks cement  
Pulled pipe to 180' mixed 20 sacks cement  
capped hole with 10 sacks cement

**RECEIVED**  
STATE CORPORATION COMMISSION  
NOV 13 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pipe Pullers Inc.  
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Pipe Pullers Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Miller

(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of October, 1961

My commission expires December 18, 1962  
Juanita R. Myers Notary Public.



15-163-00951-0000

WELL LOG

OPERATOR C-G Drilling Co. & Oil Trading Associates, Inc. SEC. 34-10S-20W  
 WELL NAME Briggs #2 LOC. SE NE NW  
 TOTAL DEPTH 3712' COUNTY Rooks  
 COMM. May 9, 1956 COMP. May 20, 1956 STATE Kansas  
 RIG NO. 1 ELEVATION 2127' R.B.  
 CASING: Left in hole 186' 8-5/8" OD Surface Casing PRODUCTION: Plugged & Abandoned  
 And 1007' 5-1/2" OD Casing

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	1040	Shale		
1040	1280	Sand		
1280	1568	Red Bed		
1568	1606	Anhydrite		
1606	1925	Shale & Shells		
1925	3704	Lime & Shale	0° - 2500	DST 3431-3469'
3704	3712	Shale & Lime	0° - 2750	DST 3483-3489'
			0° - 3000	DST 3540-3580'
			0° - 3250	DST 3582-3600'
			0° - 3500	

RECORDED  
 NOV 13 1961  
 CONSTITUTION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 COUNTY OF SEDGWICK ) SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway  
 G. F. Galloway

THIS 9th day of November, 1961.

Vicky Jacobs  
 Vicky Jacobs - Notary Public



SUBSCRIBED AND SWORN TO, BEFORE ME,

My commission expires:  
 May 20, 1963