

15-163-20099-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 34 Twp. 10S Rge. (E) 20 (W)

Location as "NE/CNW/SE" or footage from lines. SW NE SE

Lease Owner Rains & Williamson Oil Co., Inc.

Lease Name VEATCH Well No. 1

Office Address 1425 Wichita Plaza - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-9 19 68

Application for plugging filed 4-9 19 68

Application for plugging approved 4-9 19 68

Plugging commenced 4-9 19 68

Plugging completed 4-9 19 68

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production -- 19 --

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols, Moreland, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3724 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	224'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Spotted 70 sacks cement at 750'. Mudded back to 240'.
Spotted 20 sacks cement. Mud back to 40', set solid bridge
and capped with 10 sacks, 2 sacks in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

Address 1425 Wichita Plaza - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God:

(Signature) Wilson Rains Wilson Rains

1425 Wichita Plaza - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of April, 19 68

My commission expires June 30, 1971

Sherry Gish
Notary Public.

15-163-20099-0000

ROTARY DRILLING LOG

Operator: Rains & Williamson
Oil Co., Inc.
VEATCH #1
SW NE SE Sec. 34-10S-20W
Rooks County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.
Commenced: 4-1-68
Completed: 4-9-68
Remarks: Set 8-5/8" surface
casing at 224'
w/150 sacks GL-3.

Formations

Surface Soil and Sand	44'
Shale	1018'
Sand	1223'
Red Bed	1535'
Anhydrite	1587'
Shale and Shells	1950'
Shale and Lime	2235'
Lime and Shale	2750'
Shale and Lime	3255'
Lime and Shale	3295'
Lime	3575'
Lime and Shale	3640'
Lime	3724'
Rotary Total Depth (D & A)	3724'


RECEIVED
STATE CORPORATION COMMISSION
APR 17 1968
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log
is true and correct to the
best of our knowledge and
belief.

RAINS & WILLIAMSON OIL CO., INC.


Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of
Kansas, County of Sedgwick, this 16th day of April, 1968.


Sherry Gish Notary Public

My Commission Expires:
June 30, 1971