

15-163-01157-0001

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER OWWO

LEASE NAME HARLAN

WELL NUMBER 1

SPOT LOCATION NE NW SW

SEC. 34 TWP. 10S RGE. 20 (E) OR (W)

COUNTY Rooks

DATE WELL COMPLETED 11-13-81

PLUGGING COMMENCED 8-8-83

PLUGGING COMPLETED 8-11-83

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR MIDCO Exploration, Inc.

ADDRESS 200 E. 1st. St. - Suite 411  
Wichita, Kansas 67202

PHONE #(316) 267-3613 OPERATORS LICENSE NO. 5254

CHARACTER OF WELL Oil  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dist #6 - Dennis Hamel

IS ACO-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? Filed with ACO-1

PRODUCING FORMATION Lansing & Arbuckle DEPTH TO TOP 3737 BOTTOM 3849 T.D. 3849

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Oil & Water	3737	3849	4 1/2 10.5#	3846'	None

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET 8-8-83 Dennis Hamel on location. Mixed 50 sacks 50-50 poz. 6% gel, 1 hull, 10 gel, 100 sacks cement, 1 hull. Put in 4 1/2 casing @ 900#. Mixed 150 poz 50-50, 6% gel put down 8 5/8 casing @ 800#. Finished @ 3:00 p.m. 8-11-83 Push plug to 40', dump 5 gals sand, mixed sand & cement (15 gals) fill hole. Cut 8 5/8 head off, put plate over well & welded. Finished @ 12:30 p.m. Called Dennis Hamel.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Allied Cementing Co., Inc. LICENSE NO. \_\_\_\_\_  
ADDRESS Box 31 - 332 W. Wichita, Russell, Ks. 67665

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, SS.

Lloyd Davis (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Lloyd Davis  
(ADDRESS) Russell, Kansas.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 20th DAY OF September, 1983

Barbara L. Zurowski  
NOTARY PUBLIC  
Barbara L. Zurowski

MY COMMISSION EXPIRES: January 20, 1986

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 21 1983  
WICHITA, KANSAS

FORM CP-4  
REVISED 06-83