

15-163-00338-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County. Sec. 34 Twp. 10S. Rge. 20 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE SW
Lease Owner Barnett Drilling, Inc., et al
Lease Name Harlan Well No. 1
Office Address 623 First National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 16 1951
Application for plugging filed September 16 1951
Application for plugging approved September 16 1951
Plugging commenced September 16 1951
Plugging completed September 16 1951
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3720 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Pipe		0	117 ft.	8-5/8"	117 ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3720 feet to 115 ft. Set wooden plug at 115 feet.
Filled with one-half sack of hulls and 15 sacks of cement to 40 feet and set top wooden plug at 40 feet. Dumped one-half sack of hulls on plug and filled to bottom of cellar with 10 sacks of cement.

SEP 22 1951

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Barnett Drilling, Inc.
Address 623 First National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

F. R. Stubblefield (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. R. Stubblefield
623 First National Bank Building
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 21 day of September, 1951

Adelaide Olivier
Notary Public.

My commission expires May 12, 1955

23-5091-s 8-50-10M

PLUGGING
FILE SEC 34 T 10 R 20W
BOOK PAGE 119 LINE 30

15-463-00338-0000

BARNETT DRILLING, INC.
 LOG OF HARLAN WELL NO. 1
 NE $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$ SECTION 34-10S-20W, ROOKS COUNTY, KANSAS

Date Commenced: September 2, 1951

Date Completed: September 16, 1951

Formation	From	To	Remarks
Shale	0	90	Set 8-5/8" Surface Pipe at 147 feet, Cemented with 125 Sacks
Sand	90	105	
Shale	105	147	
Shale	147	550	
Sand	550	600	
Shale	600	700	
Sand	700	850	
Shale and Shells	850	1010	
Sand	1010	1215	
Shale and Shells	1215	1537	
Anhydrite	1537	1575	
Shale and Shells	1575	1890	
Shale and Lime	1890	3305	
Lime	3305	3640	
Conglomerate	3640	3712	
Arbuckle	3712	3720	
Total Depth		3720	Dry and Abandoned

CERTIFICATE.

I, F. R. Stubblefield, of Barnett Drilling, Inc., hereby certify that to the best of my knowledge and belief, the above is a true and correct log of the Harlan Well No. 1, located in the NE $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$ Section 34-10S-20W, Rooks County, Kansas.

F. R. Stubblefield

Subscribed and sworn to before me, in and for the County of Sedgwick, State of Kansas, this 21st day of September, 1951.

Adelaide Olivier
Notary Public

My Commission Expires May 12, 1955.

PLUGGING
 FILE SEC 34-10-200
 BOOK PAGE 110 LINE 3e