


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Graham County. Sec. 3 Twp. 10S Rge. 21 (~~EX~~ (W))  
Location as "NE/CNW&SW&" or footage from lines 55' E of C SW SW SW  
Lease Owner Union Texas Petroleum, Inc.  
Lease Name C. L. Miller Well No. 10  
Office Address Drawer D Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed April 22, 19 62  
Application for plugging filed April 28, 19 64  
Application for plugging approved April 29, 19 64  
Plugging commenced June 2, 19 64  
Plugging completed June 12, 19 64  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production July 1, 19 62  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation Arbuckle Depth to top 3822' Bottom 3824' Total Depth of Well 3824 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	200	None
				5 1/2	<del>None</del> 3824	None
					<i>ETCC</i>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Cleaned out cellar.

Rigged up. Sanded to 3790'. Dumped 5 sacks of cement. Shot pipe at 600', 500', 400', 300' and 200'. Circulating with cement.

Cut off head. Build rock bridge at 225'. Dumped 28 sacks of cement.

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN 18 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Harold Rosenberg (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Rosenberg  
Drawer D, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of June, 19 64

My commission expires Feb. 7, 1966

Ethel L. Koch  
Notary Public.



DRILLER'S LOG

Company: Anderson-Prichard Oil Corp.  
 Farm: Miller Well No. 10

55 ft. E C - SW/4 SW/4 SW/4  
 Sec. 3, Twp. 10S, Rge. 21W,

Total Depth: 3824'

County: Graham,  
 Kansas

Comm: 3-17-52 Comp: 3-28-52

Contractor: Glenn W. Peel

Elevation:

Casing:

8 5/8" 200' cem.  
 5 1/2" 3824' cem.

Production:

Figures below indicate bottom of formations

Surface Clay	0 -	40
Sand & shale		100
Shale		1715
Anhydrite		1755
Shale & Shells		2350
Lime & Shale		2475
Lime		2725
Lime & Shale		3415
Lime		3520
Lime & Shale		3590
Lime		3824
Total Depth		3824

This is to certify that the above information is, to the best of our knowledge true and correct.

GLENN W. PEEL

BY: *Glenn W. Peel*

SUBSCRIBED AND SWORN to before me this 29<sup>th</sup> day of March, 1952.

My commission expires June 4, 1955

*Marion M. Hart*  
 Notary Public