

15-065-01689-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 3 Twp. 10 Rge. 21W (E) (W)

Location as "NE/CNWxSWx" or footage from line 990 FNL and 990 FEL

Lease Owner Phillips Petroleum Company

Lease Name Tribble Well No. 3

Office Address Box 287, Gt. Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed July, 1951 19

Application for plugging filed 5-2-66 19

Application for plugging approved 5-4-66 19


Plugging commenced 5-17-66 19

Plugging completed ~~5-19-66~~ 5-19-66 19

Reason for abandonment of well or producing formation uneconomical

If a producing well is abandoned, date of last production Nov. 1965 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well J P Roberts, Administrator

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well PTD 3632 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	1634	
				5 1/2	3822	2510

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand 3632-3480, 5 sx cement 3480-3440.

Shot and recovered 2510' of 5 1/2" casing.

Set rock bridge 500' to 490'; 25 sx cement 490' to 425'; mudded hole to 30', 10 sx cement 30' to base of cellar. Well P&A. 5-19-66.

RECEIVED

STATE CORPORATION COMMISSION

MAY 26 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Unit
Address Box 364, Gt. Bend, Kan

STATE OF Kansas, COUNTY OF Barton, ss.

A. T. Slagle, Dist. Supt. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. T. Slagle

Box 287, Gt. Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of May, 19 66

Laura Lee Parks
Notary Public.

My commission expires 10-27-69

Phillips

3-10-21W 15-065-01689-0000

EXPLORATION RECORD

Lease Trible

Well 3 ✓

Formation Name	Top	Base	Remarks
Surface sand and clay	0	406	
Shale, sand and lime streaks	406	820	
Sand and shale	820	1025	
Shale, sand and pyrite	1025	1225	
Shale, sand, pyrite and redbed	1225	1535	
Shale and pyrite	1535	1660	
Redbed and anhydrite	1660	1780	
Lime and shale	1780	1939	
Shale	1939	2125	
Shale and shells	2125	2292	
Lime and shale	2292	2560	
Lime and shale streaks	2560	2645	
Lime and shale	2645	3821	
Lime	3821	3831	