


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Graham County. Sec. 3 Twp. 10S Rge. 21W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW SE
Lease Owner Phillips Petroleum Company
Lease Name Morel Well No. 3
Office Address Box 287, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 30, 1951 19
Application for plugging filed February 17, 1969 19
Application for plugging approved February 18, 1969 19
Plugging commenced March 30, 1969 19
Plugging completed April 2, 1969 19
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production March 16, 1968 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols PBTD 3795'
Producing formation See below Depth to top _____ Bottom _____ Total Depth of Well 3887 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Oil-Water	3849	3887	8-5/8"	1815'	-
LKC	Oil-Water	3532	3761	5-1/2"	3869'	2544'
Toronto	Oil-Water	3517	3527			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

CIBP set @ 3795'. Knight CPU pushed 5 1/2" wood plug to 3400'. Dmpd sand 3400-3350', 5 sx cmt 3350-3315'. Shot 5 1/2" csg @ 2544' & pulled csg (2544'). Mudded hole 3315-1600'. Spotted 35 sx Jel mud 1600-200', 60 sx MR cmt 200' to surface.

RECEIVED
STATE CORPORATION COMMISSION
APR 9 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. A. T. Slagle (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. T. Slagle Dist. Supt.

Box 287, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of April, 1969

Lura Lee Parks

Notary Public.

15-065-01683-0000

Form No. 873

Formation Record

Lease **Morel**

Well No. **3**

FROM	TO	Formation	REMARKS
0	587	Surface Sand and Clay.	Elevation: Ground 2285'
587	865	Lime and Shale.	Derrick Floor 2287'
865	1114	Sand, Shale & Gyp.	R.K.B. 2289'
1114	1805	Shale, Pyrite & Lime	
1805	1460	Shale, Pyrite & Redbed	
1460	1610	Redbed and Pyrite	
1610	1762	Redbed & Shale	
1762	1812	Anhydrite	Top Anhydrite 1763' Base 1810'
1812	1880	Redbed	
1880	2098	Redbed and Shells	
2098	2825	Lime and Shale	
2825	2461	Shale and Shells	
2461	2567	Shale	
2567	2764	Lime and Shale	
2764	2868	Lime, Shale and Sand	
2868	3034	Lime and Shale	
3034	3131	Shale and Shells	
3131	3332	Shale and Lime	
3332	3508	Lime and Shale	Top Heebner 3492'
3508	3773	Lime	Tops: Toronto 3511' LKC 3529'
3773	3858	Lime and Shale	Drum 3664' Base LKC 3758'
			Arbuckle 3849'

RECEIVED
 STATE CORPORATION COMMISSION
 APR 9 1969
 CONSERVATION DIVISION
 Wichita, Kansas