

15-065-01677-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

GRAHAM County. Sec. 3 Twp. 10S Rge. (E) 21 (W)

Location as "NE/CNW&SW&" or footage from lines SE SE SW  
Lease Owner UNION TEXAS PETROLEUM  
Lease Name MILLER Well No. 8  
Office Address 1740 BRAODWAY, DENVER, COLORADO  
Character of Well (completed as Oil, Gas or Dry Hole) OIL WELL  
Date well completed AUGUST 10 19 51  
Application for plugging filed MARCH 30 19 66  
Application for plugging approved 19  
Plugging commenced APRIL 1 19 66  
Plugging completed MAY 9 19 66  
Reason for abandonment of well or producing formation DEPLETED

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS  
Producing formation Depth to top Bottom Total Depth of Well 3854 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	197	NONE
				5 1/2"	3852	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4-1-66 PUMPED 20 SACKS GEL MUD AND MUD STARTED CIRCULATING OUTSIDE OF SURFACE PIPE.

4-2-66 PUMPED 63 SACKS CEMENT DOWN 5 1/2" CASING.

5-4-66 STATE SUPERVISOR CHECKED WELL AND FOUND FLUID AT 75', PLUG AT 2028'.

5-9-66 RAN 2" TUBING TO 600', PUMPED 8 SACKS QUICK SET CEMENT, WAITED ONE HOUR, THEN PUMPED 65 SACKS CEMENT TO BASE OF CELLAR.

13 1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.  
Address BOX 562, GREAT BEND, KANSAS 67530

STATE OF KANSAS COUNTY OF BARTON, ss.  
T. L. NUTT (employee of owner) or former owner

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

BOX 562, GREAT BEND, KANSAS 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 10TH day of JUNE 19 66

My commission expires JULY 31, 1966

Mary M. Guerin  
Notary Public.

15-065-01677-0000

DRILLER'S LOG

Company: Anderson-Prichard Oil Corp.

SE/4 SE/4 SW/4  
Sec. 3, Twp. 10S, Rge. 21W,  
County, Graham,  
Kansas

Farm: Miller Well No. 8  
Comm: 8-1-51 Comp: 8-10-51

Total Depth: 3854'  
Contractor: Glenn W. Peel  
Casing:

Elevation:

8 5/8" 197' cem.  
5 1/2" 3852' cem.

Production:

Figures below indicate bottom of formations

Surface Clay	0 -	21
Sand		37
Shale & Shells		640
Sand		915
Shale & Shells		1770
Anhydrite		1812
Shale & Shells		2255
Lime & Shale		2420
Lime w/shale streaks		2560
Broken Lime		2670
Lime & Shale		2975
Shale		3135
Lime & Shale		3490
Lime		3850
Conglomerate		3851
Arbuckle Lime		3854
Total Depth		3854

This is to certify that the above information is, to the best of our knowledge true and correct.

GLENN W. PEEL

BY: Joseph Matthews

SUBSCRIBED AND SWORN to before me this 14<sup>th</sup> day of August, 1951.

My commission expires June 4, 1955

Marion M. Herbert  
Notary Public