


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Graham County. Sec. 3 Twp. 10S Rge. 21 (W)W  
Location as "NE/CNW/SW" or footage from lines. NE SW SW  
Lease Owner: Union Texas Petroleum Corporation  
Lease Name: Miller Well No. 2  
Office Address: Drawer D, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed November 1, 19 50  
Application for plugging filed July 13, 19 64  
Application for plugging approved July 14, 19 64  
Plugging commenced July 22, 19 64  
Plugging completed July 24, 19 64  
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production October 2, 19 63  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation Arbuckle Depth to top 3851' Bottom 3853' Total Depth of Well 3854 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	256'	None
				5 1/2	<del>None</del> 3854'	None
					RTKLL	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in pulling unit. Cleaned out cellar. Found cement in surface casing. Pulled on pipe. No recovery.

Plugged off bottom with sand and 5 sacks of cement.

Pumped in 35 sacks of mud and 70 sacks of cement. Well completed.

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUL 30 1964  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Harold Rosenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Rosenberg  
Drawer D, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of July, 1964

Esther L. Focho  
Notary Public.

My commission expires Feb. 7, 1966



MILLER NO. 2 WELL

LOCATION: NE $\frac{1}{4}$  SW $\frac{1}{4}$  SW $\frac{1}{4}$  3-10S-21W  
Graham County, Kansas

OPERATOR: Anderson-Frithard Oil Corp.

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: Ran 12 jts., 258.95' 8-5/8" casing  
cemented at 256' with 175 sacks  
bulk cement. 2 c.c.

OIL STRING: Ran 122 jts., 3870' 5 $\frac{1}{2}$ " casing  
cemented at 3854' with 125 sacks  
cement.

SPUDED: 10-5-50

COMPLETED: 10-15-50

L O G

(Figures indicate bottom of formation)

0	to	256	Surface
		865	Shale
		1250	Shale and sand
		1490	Sand
		1760	Shale and red bed
		1798	Anhydrite
		2075	Shale
		2710	Shale and lime
		3170	Shale
		3215	Lime and shale
		3330	Shale
		3415	Shale and lime
		3475	Lime
		3535	Shale and lime
		3857	Lime
		3857	Total Depth.

**RECEIVED**  
STATE CORPORATION COMMISSION

JUL 14 1964

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Miller No. 2 well as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

BY Richard Hindery

Sworn and subscribed before me  
this 18th day of October, 1950.

Winnifred L. Gingles  
Notary Public

My commission expires November 29, 1950.