

15-065-20267-0000

Form CP-3  
Rev. 6-4-68

KANSAS

24

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 17 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Svoboda Well No. 1

Location NE-NW-NE Sec. 22 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3803'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor L. J. Dreiling & Sons, Incorporated.

Address R. R. #2, Victoria, Kansas. License No.       

Operation Completed: Hour 11:15 AM Day 14 Month 10 Year 1969

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 125 Sx.  
Top of Dakota section @ 660'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 100 Sx. cement thru  
DP from 900' to 575'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from  
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 10/17/69  
INV. NO. 692-11