

15-065-03033-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1962
09-10-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name C & G Drg Co
Complete Address: 107 Rule Bldg Wichita, Kansas
Lease Name Hunt-Behrens Well No. 5
Location NE SE SE Sec. 12 Twp. 10 Rge. (E) (W) 21
County Graham Total Depth 3824

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Globe Cementing Co

Address: Plainville, Kans License No.

Operation Completed: Hour 3PM Day 6 Month 9 Year 62

The Above well was plugged as follows:

8 5/8" 181' circulated with cement - 5 1/2" 3814' with 125 sax cement - DV tool
at 1776' - circulated with cement from 1776' to 0' (450 sax cement & 35 sax
strata crete) - no pipe recovery.

Pumped hole full heavy gel mud (35 sax Gel), pumped wiper plug followed by
70 sax cement - 1200# pump pressure on mud - 800# pump pressure on cement.
cement 560' to 0'.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 9/1/62
INV. NO. 5664-W