

15-065-03033-0001

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leben Drilling, Incorporated,
Complete Address Box #486, Great Bend, Kansas.
Lease Name Beiker Well No. 5
Location NE-SE-SE Sec. 12 Twp. 10 Rge. (E) (W) 21
County Graham Total Depth 3824'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Sun Oil Well Cementing, Inc.,
Address Hays, Kansas. License No.
Operation Completed: Hour 3:30 PM Day 6 Month 10 Year 1970
22 9

The above well was plugged as follows:

No amount of 8 5/5" Surface casing indicated.

3814'--5 1/2" Production casing cemented on bottom with open hole completion then plugged back to 3550' with no record of perforations above plug. 5 1/2" had been squeezed thru perforations in the anhydrite to surface.

Squeezed 5 1/2" initially with 1/2 sack hulls and followed with 12 Sx. cement then 25 sacks gel and followed with 80 Sx. cement. Maximum pump-in pressure--400#. Final shut-in pressure--150#. Checked top of cement in well 9/24/70 @ 100'. On 10/6/70 filled 5 1/2" casing to surface with Redi-Mix cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols

Well Plugging Supervisor

DATE 10/9/70INV. NO. 2657-W