

15-065-00768-0001

Form CP-3
Rev. 6-4-68

KANSAS

24

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leben Drilling, Incorporated,

Complete Address Box #486, Great B end, Kansas.

Lease Name Beiker Well No. 3

Location SE-SW-SE Sec. 12 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3862'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sun Oil Well Cementing,

Address Hays, Kansas. License No.

Operation Completed: Hour 1:45 PM Day 22 Month 9 Year 1970

The above well was plugged as follows:

170'--8 5/8" Surface casing, cement circulated.

3839'--5 1/2" casing cemented on bottom. Open hole completion. 5 1/2" has been squeezed
thru perforations from anhydrite to surface.

Squeezed 5 1/2" casing initially with 1 sack hulls and followed with 12 Sx. cement then
27 sacks gel and followed with 15 Sx. cement. Maximum pump in pressure--2200#.

Final shut-in pressure--1000#.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols

Well Plugging Supervisor

INVOICED

DATE 10-5-70INV. NO. 2021-W