

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SW SE

SEC. 22 TWP. 10 RGE. 21 *W*

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Svoboda

Operator Jones Shelburne & Farmer Address Russell, Kans

Field _____ County Graham

Total Depth 3745 Feet.

(Describe briefly the manner in which the well was plugged)

85/8" at 165' circulated with cement - 5 1/2" at 3743' with
100 sax cement behind. Perf at 3730'.
Filled with chat to 3720', set 4 sax cement with dump bailer,
pulled 3028' 5 1/2", filled hole with mud to 165', set rock
and 15 sax cement, mud to 35', set rock and 10 sax cement
to bottom cellar.

Edwin Petty
District Conservation Agent

Date 5-3-52

PLUGGING
FILE SEC 22 T 10 R 21W
BOOK PAGE 13 LINE 40

RECEIVED
STATE CORPORATION COMMISSION
MAY - 5 1952
OS - OS - 52
CONSERVATION DIVISION
Wichita, Kansas