

15-065-00768-0000

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSIONSEP 10 1962
09-10-62
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name C & G Drg Co

Complete Address: 107 Rule Bldg Wichita, Kansas

Lease Name Hunt-Behrens Well No. 3

Location SE SW SE Sec. 12 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3856

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Globe Cementing Co

Address: Plainville, Kans License No.

Operation Completed: Hour 12 Noon Day 6 Month 9 Year 62

The Above well was plugged as follows:

8 5/8" 170' circulated with cement - 5 1/2" 3839' with 125 sax cement - perf at 1746' and circulated with cement from 1746' to cellar - 450 sax cement & 35 sax strata crete - no pipe recovery.

Pumped hole full heavy gel mud (30 sax Gel) at 1750# pump pressure - pumped wiper plug followed by 70 sax cement - pump pressure 1750#.

Cement 560' to 0'.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

9/11/62

INV. NO.

5666-11

Signed:

Well Plugging Supervisor