

15-065-03034-0000

Form CP-3  
Rev. 6-26-62

10  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

SEP 10 1962  
09-10-62  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name C & G Drg Co

Complete Address: 107 Rule Bldg Wichita, Kansas

Lease Name Hunt-Behrens Well No. 6

Location SW NE SE Sec. 12 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3806

Abandoned Oil Well x Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Globe Cementing Co

Address: Plainville, Kansas License No.

Operation Completed: Hour 5PM Day 6 Month 9 Year 62

The Above well was plugged as follows:

8 5/8" 180' circulated with cement - 5 1/2" 3797' with 125 sax cement - DV tool  
at 1730' and circulated from 1730 to 0' with 450 sax cement and 35 sax  
stratacrete - no pipe recovery.

Pumped hole fülle heavy gel mud ( 40 sax Gel) 500# pump pressure - pumped  
wiper plug followed by 70 sax cement - pump pressure 1800# - cement 560' to 0'

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: *Edon Perry*  
Well Plugging Supervisor

DATE 9/11/62

INV. NO. 5663-W