

15-065-01148-0000

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 - - (of this well)

Operator's Full Name A.L. Abercrombie Inc.

Complete Address 801. Union Center. Wichita Ks.

Lease Name Ben Hayes "A" Well No. # 1

Location SE-SW-SW Sec. 22 Twp. 10 Rge. 21 (E) (W) X

County Graham Total Depth 3785

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereafter indicated

Plugging Contractor A.L. Abercrombie Inc.

Address 801. Union Center. Wichita Ks License No.

Operation Completed: Hour 1:00 ^{PM.} Day 7 Month Oct Year 1980

The Above well was plugged as follows:

KB. 2191. DT. 1500. SP. 281' 7.8 5/8" cwe. 150 sx.
4 1/2" casing set @ 3778. 1 1/25. 9x. Perm Plug. @ 3400"
D.V. Tool @ 1675. Cem. To Top Pumped down. 4 1/2"
75 sx cem. 50/50 Por 6 P. Gel. Max. Pres. 500 lbs.
By Sum Cementing.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10-14-80
INV. NO. 3354-w

Signed: [Signature]
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION
OCT - 9 1980
CONSERVATION DIVISION
WICHITA, KANSAS

CONTRACTOR'S WELL LOG

COMPANY: A. L. Abercrombie, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 FARM: HAYES #1
 LOCATION: SE SW SW Sec. 22-10S-21W
 Graham County, Kansas
 COMMENCED: August 10, 1963
 COMPLETED: August 21, 1963

| | | |
|------|------|--------------------|
| 0 | 230 | Sand & Shale |
| 230 | 1297 | Shale & Shells |
| 1297 | 1895 | Shale & Lime |
| 1895 | 2195 | Shale & Shells |
| 2195 | 2360 | Lime & Shale |
| 2360 | 2455 | Lime |
| 2455 | 3316 | Lime & Shale |
| 3316 | 3785 | Lime |
| 3785 | | Rotary Total Depth |

Set 8-5/8" surface at 231' w/150 sx Pozmix Sunset Cement

Set 4-1/2" casing at 3778, lower stage cemented with 125 sx salt saturated Pozmix. D-V Tool set at 1670' with 450 sx Pozmix, 4% gel.

ELEVATION: 2197' D. F.
 2197' K. B.
 2191' G. L.

WELEX LOG TOPS:

| | | |
|------------------|-------|---------|
| Anhydrite | 1657' | (+ 540) |
| Bottom Anhydrite | 1718' | (+ 479) |
| Topeka | 3219' | (-1022) |
| Heebner | 3428' | (-1231) |
| Toronto | 3450' | (-1253) |
| Lansing | 3466' | (-1269) |
| Base Kansas City | 3700' | (-1503) |
| Arbuckle | 3776' | (-1579) |

RECEIVED
 STATE CORPORATION COMMISSION
 AUG - 5 1980
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, B. Lynn Herrington, do hereby certify that the above and foregoing is a true and correct copy of the log of the HAYES #1, SE SW SW, Section 22-10S-21W, Graham County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

B. Lynn Herrington
 B. Lynn Herrington

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 19th day of September, 1963.

Leah Faye Heike
 Leah Faye Heike, Notary Public