

FO:   
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21290-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 3-10S-21W  
990 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: MILLER Well Number: 1  
County: GRAHAM Total Vertical Depth: 4040 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 4514 COLE AVE., STE 804, LB 30  
DALLAS, TX 75205

Production Casing Size: 5.5 feet: 3873  
Surface Casing Size: 8.625 feet: 248

#131<sup>30</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/11/2003 2:00 PM  
Plug Co. License No.: 7049 Plug Co. Name: RAPID WELL SERVICE INC  
Proposal Rcvd. from: ALLEN BANGERT Company: RAPID WELL SERVICE INC Phone: (785) 483-3362

Proposed Plugging Method: Ordered 225 sxs cement - 14 sxs gel - 800# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 07/11/2003 6:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 248' w/160 sxs cement. 5 1/2" casing at 3873' w/125 sxs cement.  
D.V. at 1750' w/400 sxs.cement.  
Ran wireline to 3350'.  
Ran tubing to 3295' - spotted 25 sxs cement with 150# hulls.  
Pulled tubing to 3072' - spotted 14 sxs gel with 200# hulls.  
Pulled tubing to 1750' - circulated with 160 sxs cement with 350# hulls.  
Pulled all tubing and topped off with 25 sxs cement. Held.  
Tied to 8 5/8" x 5 1/2" annulus - pressured to approximately 400#.  
Found cement at top of wellbore. Took no cement.  
Total of 210 sxs 60/40 pozmix - 10% gel - 14 sxs gel and 700# hulls.

RECEIVED  
AUG 04 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. KELLER TANK-WATER.

Plugged through: TBG

District: 04

Signed

Roger L Moses  
(TECHNICIAN)

INVOICED

DATE 8.5.03

INV. NO. 2004060333

Form CP-2/3

JUL 31 2003

COLLINS & COLLINS OIL CO. REPLACEMENT CARD: 3-10-21W  
 1007 CODY A #1 MILLER NW SE SW  
 HAYS, KS. 67601

CONTR DREILING OIL CO., INC. CTY GRAHAM

GEOL LAWRENCE F. GRAY FIELD COOPER

2256 KB CM 8/6/80 CARD ISSUED 2/12/81 IP D&A/ARB  
 2257 GL 1/20/81

+	+
+	+

API 15-065-21,290

LOG	TOPS	DEPTH	DATUM
SC		1733	+ 523
HEEB		3464	-1208
TOR		3488	-1232
LANS		3504	-1248
B KC		3728	-1472
ARB		3820	-1564
TD		3875	-1619

8-5/8" 248/160sx, 5 1/2" 3873/125sx  
 NO DST'S  
 MICT - CO, PF (ARB) 7/3834-3836, 8/  
 3821-3823, AC 500 GAL, SET BP @ 3750',  
 PF (LANS) 4/3664-3726 OA, AC 7000 GAL,  
 P&A

CORRECTION: 8/31/81 - WAS C SE SW

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

15-065-21,290  
 8/31/81  
 C. S. W.