

1-30

4-050263

API Number: 15-065-21223-00-02

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SE NE SW /4 SEC. 04, 10 S, 21 W
1650 feet from S section line
2970 feet from E section line

Operator license# 3456

Lease: Towns Well # 4

Operator: AFG Energy, Inc.

County: Graham 125.51

Address: P.O. Box 458
Hays, Kansas 67601
913-625-6374

Well total depth 3862 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 185 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing, Inc. License# -

Address:

Company to plug at: Hour: A.M. Day: 30 Month: January Year: 1997

Plugging proposal received from: Terry Piesker

Company: Phone:

Were: 8 5/8" set at 185' w/185 sxs. 5 1/2" set at 3859' w/250 sxs.
Anhydrite at 1764' - D.V. set at 1762' w/450 sxs. Open hole.
Arbuckle '3859' - 3862'.

RECEIVED
ST. CORPORATION COMMISSION
FEB 10 1997

RECEIVED
KANSAS CORP COMMISSION
FEB 12 1997

02-12-97

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [X], Part [], None []

Conservation Division
Topeka, Kansas

Completed: Hour 10:15A.M., Day: 30, Month: January, Year: 1997

Actual plugging report: Backside full pressured to 700 P.S.I. Held. Tied onto 5 1/2" casing pumped and squeezed 275 sxs cement 60/40 pozmix - 10% gel - 500# hulls. Max. P.S.I. 1200#. S.I.P. 200#.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2294 GL

I did [X] / did not [] observe the plugging.

Marvin Miller (agent)

INVOICED

Form CP-2/3

DATE FEB 13 1997

INV. NO. 47555
1-30