

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21221-00-00  
Spot: SESENW Sec/Twnshp/Rge: 4-10S-21W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: TOWNE Well Number: 1  
County: GRAHAM Total Vertical Depth: 3928 feet

Operator License No.: 6931  
Op Name: BOWMAN OIL COMPANY  
Address: 805 CODELL RD.  
CODELL, KS 67663

Conductor Pipe: Size feet: \$127.66  
Surface Casing: Size 8.62 feet: 248 150 SX CMT  
Production: Size 5.5 feet: 3925 200 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/09/2002 9:00 AM  
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY  
Proposal Rcvd. from: PAUL BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Perf casing at 1775' and 1100'.  
Ordered 400 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 05/09/2002 12:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 2300'. Spotted 250 sxs cement with 300# hulls to circulate cement at surface.  
POOH with tubing and squeezed casing with 100 sxs cement.  
Max. P.S.I. 300#.  
Squeezed 8 5/8" S.P. with 25 sxs cement plus 100# hulls.  
Max. P.S.I. 500#.

RECEIVED

JUN 26 2002  
06-26-02  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel  
(TECHNICIAN)

INVOICED

DATE 6-27-02

TRK NO. 2002062014

Form CP-2/3

JUN 18 2002

replacement card

H & P OIL EXPL  
HILL CITY KS

4-10S-21W  
SE SE'NW

#1 TOWNE

site: 2-1/2 S & 5-1/2 W OF PALCO KS  
contr: EMPHASIS OIL OPER

cty: GRAHAM  
field: COOPER

API 15-065-21221

well:  
fr date 03/26/80    opd date 04/02/80    drlg comp 04/08/80    card issued 03/26/81    last revised 09/14/98


ELV: NA  
tops.....depth/datum  
RTD.....3900  
NO TOPS RPTD

IP status:  
OIL, P 10 BOPD, ARB, INTV NA, 09/01/80  
INFO RELEASED: 9/14/98 - WAS OIL WELL - TEMP  
COMP  
CSG: 8-5/8" 200+, 4-1/2" 3900  
NO CORES OR DSTS  
MICT - CO, PF (ARB) INTV NA, AC'D, SO, POP, OIL  
WELL (POTENTIAL NOT RPTD), 9/1/80 - NO OTHER  
INFO RELEASED BY OPERATOR OR ON KCC  
RECORDS; ALL REQUESTS FOR INFO DENIED

MANICE