

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065 - 21,937 - 0000

NE, Sec. 4, T 10 S, R 21 W/E
2350 feet from N/E section line
1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5354

Lease Name Deyoung Well # 2

Operator: Southern States Oil Company
Name & Box 1365
Address Great Bend, Ks.

County Graham

Well Total Depth 3885 feet 126.27

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 342

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Woodman & Iannitti License Number 5122,

Address Box 308, Great Bend, Ks.

Company to plug at: Hour: 6 AM Day: 3 Month: March Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Vernon Dunlap

(company name) Woodman & Iannitti (phone) (316) 792-2921

were: Order 210 sks cement 50/50 pozmix 6% gel 3% cal.cl. 1 sk hulls, 1-8 5/8 plug

1 sk flow seal. Heavy mud between all plugs. Pump cement down drill pipe.

Elevation 2282 Anhydrite 1739-83 Arbuckle 3862 Dakota 1600

Signed Dale F. Balthazor
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:45 AM Day: 3 Month: March Year: 19 84

ACTUAL PLUGGING REPORT Circulated @ 3860 for 45 minutes

1st plug 25 sks @ 3860

2nd plug 25 sks @ 1750

3rd plug 100 sks @ 980 mixed with 1 sk flow seal

4th plug 40 sks @ 400 1 sk hull push plug to 40

5th plug 10 sks @ 40

Remarks: 10 sks in Rat Hole

Gilbert Balthazor witnessed this plug.

Cemented by: Sun

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1984

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed Dale F. Balthazor ✓
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 3-14-84

INV. NO. 0251

3-3-84