

5-9 15-163-00411-00-01

6 050059

D, 8912

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NW, SEC. 30, T 10 S, R 20 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245
Operator: Okmar Oil Co.
Name & Address: 970 Fourth Financial Center
Wichita, Ks.

4950 feet from S section line
4950 feet from E section line
Lease Name Raymond Well # SWD
County Rooks 124.31
Well Total Depth 3825 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 163

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Okmar License Number

Address Wichita, Ks.

Company to plug at: Hour: PM Day: 9 Month: May Year: 19 90

Plugging proposal received from Bob Grant

(company name) Okmar (phone)

were: Order 250 sks common 250 sks 65/35 poz 8% gel 3% cc 12 sks gel.
5 1/2" set at 3706'. Drill out to 2205' and cement.

Plugging Proposal Received by Bruce D. Basye (TECHNICIAN)

Plugging Operations attended by Agent?: All Part x None

Operations Completed: Hour: 11:15pm Day: 9 Month: May Year: 19 90

ACTUAL PLUGGING REPORT Drilled out 5 1/2 to 2205'. Good circ. Ran 5 sks gel and 100 sks common. Lay down tubing to 1359'. Ran 400 sks 65/35 poz 8% gel 3% cc w/ 400# of hulls in last 200 sks. Order 400 sks of 65/35 poz 8% gel 3% cc. 10:00 P.M. Pumped in 60 sks 65/35 poz 8% gel 3% cc. Cement to surf. Pulled tubing. Ran 20 sks 65/35 poz 8% gel 3% cc. Cir cement. Ran 20 sks same mix of cement 450# max., 450# shut in. 12 sks 65/35 poz 8% gel 3% cc on backside. 350# max - 350# shut in.

Remarks: Cemented by B. J. Titan (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-5-90 1990

INV. NO. 28328 CONSERVATION DIVISION Wichita, Kansas

Signed Bruce D. Basye (TECHNICIAN)

Bruce Basye