

4- 031609

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -
NW NE NW 1/4 SEC. 30, 10 S, 20 W
4950 feet from S section line
3630 feet from E section line

Operator license# 5363 Lease Raymond A well # 2

Operator: Berexco County Rooks

Address: P.O. Box 723 Well total depth 3699 feet 120.21
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 160 feet

Aband. oil well , Gas well , Input well X, SWD , D & A

Plugging contractor: Halliburton License#

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 8 Month: November Year: 91

Plugging proposal received from: George Jorgensen

Company: Berexco Phone: 913-628-6101

Were: 8 5/8" set @ 160' w/125 sx. cwc. 5 1/2" set @ 3696' w/100 sxs.
Top squeeze @ 825' w/550 sx. - 1018' w/190 sx. - 1250' w/50 sx. - 1284'
w/250 sx. TOC @ 700'. Shot in 5 1/2" @ 600' 2HPF. Perf. 3132' - 3260'.
Order 150 sx. common cement 350 sx. 60/40 posmix - 6% gel. - 500# hulls.
Halliburton Cement Company. Ows Water Trucks. Company Rig.

Plugging Proposal Received By: Don Butcher and Carl Goodrow

Plugging operations attended by agent? All], Part], None]

Completed: Hour: 3:15P.M., Day: 8, Month: November, Year: 91

Actual plugging report: Ran tubing to 3220'. Spot 100 sx. common
cement w/200# hulls mixed in. Laid down tubing to 2320'. Flow from
well was stopped. Spot 50 sx. common cement w/100# hulls mixed in.
Laid down tubing to 1920'. Circulated cement blend to surface. Laid
down tubing. Squeezed 5 1/2" casing with total of 150 sx. common cement.
150 sx. cement blend with 500# hulls mixed in to Max. P.S.I. 700#.
Close in P.S.I. 600#. Squeezed 8 5/8 annulus with 200 sx. cement blend
to Max. P.S.I. 200#. Close in P.S.I. 100#. Plug complete.

Remarks:

RECEIVED
STATE CORPORATION COMMISSION

11-27-1991
NOV 27 1991

I did not observe the plugging.

Carl Goodrow

CONSERVATION DIVISION
Wichita, Kansas

(agent)
Form CP-2/3

INVOICED
DATE 12-6-91
INV. NO. 34032