

4-070124

11-19

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1958

NE NE SW /4 SEC. 30, 10 S, 20 W
2310 feet from S section line
2970 feet from E section line

Operator license# 5134 Lease: Schneider Well # C-1

Operator: Graham Michaelis Corporation County: Rocks 119.31

Address: 211 N. Broadway
Wichita, Kansas 67202
316-264-8394
Well total depth 3671 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 210 feet
W/135 sxs.

ABAND. oil well X, Gas well, Input well, SWD., D&A

Plugging contractor: Graham Michaelis Corporation License# 5134

Address: 211 N. Broadway - Wichita, Kansas 67202

Company to plug at: Hour: 11:00 A.M. Day: 19 Month: November Year: 1998

Plugging proposal received from: Leon Kuhn

Company: Graham Michaelis Corporation Phone: 316-274-8394

Were: 5 1/2" set at 3671' w/100 sxs. Anhy. 1597' - 1637'.
Ordered out 280 sxs - 60/40 pozmix - 10% gel - 500# hulls.
Squeezed at 500' - 955' with 150 sxs.
Top of fish at 1803' - shiny spot of tubing at 1338' cedar hills.

Plugging Proposal Received by: Rich Williams
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 1:45 P.M. Day: 19, Month: November, Year: 1998

Actual plugging report: Perforated 1620' anhy. Allied pumped 240 sxs 60/40 pozmix - 10% gel with 400# hulls. Max. P.S.I. 1300#. S.I.P. 800#.
Hooked-up to backside and pumped 40 sxs 60/40 pozmix - 10% gel with 100# hulls. Max. P.S.I. 500#. S.I.P. 300#.

RECEIVED
11-25-1998

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X Elevation: GL

I did [X] / did not [] observe the plugging.

WRD

Richard Williams
(agent)

DEC 01 1998

60397