

R

6 070350

API NUMBER 15-

NE 1/4, SEC. 20, T 10 S, R 20 W

feet from S section line

feet from E section line

Lease Name ALLPHIN Well # 2

County ROOKS 120.25

Well Total Depth 3700 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor SUN OIL WELL CEMENTING License Number _____

Address BOX 169 HAYS, MO. 67601

Company to plug at: Hour: 9:00 AM Day: 10th Month: April Year: 19 85

Plugging proposal received from ISAIDOR HISNER

(company name) AMERICAN WARRIOR, INC. (phone) 913-625-5032

were: 8 5/8" - 275' SP. CUC^{SK} / 200' CNT. - 5 1/2" CSG SET @ 3666' / 125' FE

D.V. TOOL @ 1485' CNT^{SK} / 450' CNT. ALSO SQUEEZE @ 1400' / 1250' 1373' FE^{SK}, OPEN HOLE 34' FE

PERF'S @ 3562 - 3447, ORDERED 190' / 50' POZ MIX GEL - CA-CL, 20' GEL, 5' HULL'S AND 5 1/2" PLUG

PUMP IN WITH PUMP TRUCK, LOAD ANNULUS WITH CEMENT, AND PUMP IN

5 1/2" RECORD ELEV. 1900 - ANVY 1485

STATE CORPORATION COMMISSION
4-22-1985

Plugging Proposal Received by Manor Schubert
DOIC (TECHNICIAN)

APR 22 1985

Plugging Operations attended by Agent?: All Part _____ None _____

CONSERVATION DIVISION

Operation Completed: Hour: 11:15 AM Day: 10th Month: APRIL Year: 19 85

ACTUAL PLUGGING REPORT ORDERED 190' / 50' POZ MIX GEL - CA-CL, 20' GEL, 5' HULL'S,

AND 5 1/2" PLUG, PUMPED 20' CNT IN ANNULUS, MAX. PRESSURE 400 PSI, SI 250 PSI,

PUMPED IN 5 1/2" CSG. 10' CNT, 40' CNT / 2' HULL'S, 16' GEL, 1/2' HULL'S,

20' CNT (300 PSI.G), 4' GEL (400 PSI.G) 1/2' HULL'S, RELEASED PLUG,

AND 90' CNT, MAX PRESSURE 1500 PSI.G SHUT IN 1200 PSI.G.

CEMENTED BY (B.V.) SUN OIL WELL CEMENTING.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

(I do not) observe this plugging.

Signed Manor Schubert
DOIC (TECHNICIAN) 4-19-85

DATE 4-24-85

INV. NO. 7816 4-10 MAY 09 1985 JUN 12 1985

AUG 23 1985