

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01127-00-01
Spot: CSENE Sec/Twnshp/Rge: 6-10S-21W
4290 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: GERMANY Well Number: 2
County: GRAHAM Total Vertical Depth: 3890 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 232
Production: Size 5.5 feet: 3885
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/26/2001 9:30 AM

Plug Co. License No.: 32579 Plug Co. Name: PFEIFER DOZER SERVICE, LLC

Proposal Rcvd. from: DUANE ACHTERBERG Company: FLATLAND MAINTENANCE SERVI Phone: (785) 635-7335

Proposed According to KCC Rules and Regulations.
Plugging Ordered 200 sxs cement and 500# hulls.
Method: Plug thru tubing.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 04/26/2001 11:30 AM

KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 232'. 5 1/2" casing at 3885'.
RIH with tubing to 1008' - obtained fluid rate of 2 1/4 bbl/min at 250# P.S.I.
Pumped 100 sxs cement with 400# hulls - pulled all tubing.
Tied to 5 1/2" casing and squeezed 26 sxs cement to Max. P.S.I. 500#. S.I.P. 250#.
Tied to 8 5/8" S.P. and pumped 80 sxs cement to Max. P.S.I. 100#. S.I.P. 50#.
Total of 206 sxs 60/40 pozmix - 10% gel and 400# hulls.
Dakota 709' - 1009'.
Cedar Hills 1221' - 1526'.
Anhydrite 1799' - 1839'.

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 10 2001

CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY. CONTROL #20010031-001.

Plugged through: TBG

District: 04

Signed

Raymond Moses

(TECHNICIAN)

CENTURY OIL OF KANSAS, INC.
BOX 115, OBERLIN, KS.

#2 GERMANY "OWWO"

6-10-21W
SE NE NE

CONTR POE WELL SERVICE, INC. CTY GRAHAM

GEOL FIELD COOPER

E 2314 RB CM 12/21/77 CARD ISSUED 3/2/78 IP TEMP ABD

+	+	+	+
+	+	+	+
+	+	+	+

API NOT ASSIGNED

	TOPS	DEPTH	DATUM
Arh.		1799	+515
HEEB		3491	-1177
LANS		3530	-1216
ARB		3884	-1570
TD		3890	-1576

OLD INFO: OPERATOR WAS SUNRAY OIL
CORP. #2 GERMANY; SPD 7/29/53, SET
8" 232, 5" 3885; COMPLETED FOR 271
BOPD/9/4/53
DST (1) 3557-78/1', 60'Fo, 120'o&
GCM, SIP 580#
DST (2) 3721-39/26", 10'M, SIP 832#
MICT - DD 3890, 20BOPH, NAT

NEW INFO: CO, CSG PARTED IN SPOTS
TEMP ABD

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS