

6 031434

9-20
15-005-01711-0000
API NUMBER 15- 1950

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE NE, SEC. 10, T 10 S, R 21 W7E
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4629

Lease Name Bartos Well # 1

Operator: Brito Oil Co. Inc.
Name & Address: 200 E. First Suite 208
Wichita, Ks. 67202

County Graham 125.87

Well Total Depth 3873 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 259

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement License Number

Address Russell, Ks.

Company to plug at: Hour: PM Day: 20 Month: Sept Year: 19 90

Plugging proposal received from Raul Brito

(company name) Brito Oil (phone)

were: 10 3/4 set at 259 w/125 sks. 5 1/2 set at 3845 w/100 sks. 4 1/2 liner cwc.

O.H. Perf sq at 1209 - 10 w/320 sks to 1000 psi. Order 400 sks 65/35 poz 8% gel
500 lbs. hulls. Allied Cement Co. Rush water truck.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30PM Day: 20 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Sq 4 1/2 w/250 sks cement blend w/300 lbs.

hulls to max psi 1200 lbs. Close in 1000 lbs. Sq 5 1/2 - 4 1/2 annulus w/50 sks cement
w/50 lb hulls to max psi 600 lbs. Close in psi 500 lbs. Sq 8 5/8 annulus w/100 sks
cement blend w/200 lbs. hulls to max psi 500 lbs. Close in psi 400 lbs. Plug complete.

Remarks: Anhy 1760 DK 680 - 980 est.

(If additional description is necessary, use BACK of this form.)

INVOICED

STATE CORPORATION COMMISSION

DATE 10-18-90

INV. NO. 29628

OCT 17 1990 Carl Goodrow
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

Carl Goodrow FORM CP-2/3
Rev. 01-84