

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03368-00-01
Spot: N¹WNWSE Sec/Twnshp/Rge: 10-10S-21W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: MCINTIRE Well Number: 4
County: GRAHAM Total Vertical Depth: 3794 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: PO BOX 352 370 W WICHITA AVE
RUSSELL, KS 67665

Production Casing Size: 5.5 feet: 3788 100 SX CMT
Surface Casing Size: 8.625 feet: 165 100 SX CMT
31
#123

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2003 9:00 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered out 375 sxs 60/40 pozmix - 10% gel - 500# hulls.
D.V. Tool at 1716' w/500 sxs.
Fluid Level 500'.
Perfs 3478' - 3576'.
CIBP at 3600'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/21/2003 12:10 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2080'.
Allied pumped 160 sxs cement with 300# hulls. Lost circulation.
Pulled to 1200'. Allied pumped 55 sxs cement with 100# hulls.
Pulled to 900'. Allied pumped 40 sxs cement - circulated cement.
PTOH. Squeezed with 15 sxs cement.
Max. P.S.I. 700#. S.I.P. 700#.
Hooked up to backside - pumped 50 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 500#.

RECEIVED
JUL 24 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed R. Williams
(TECHNICIAN)

INVOICED

DATE 7.24.03

INV. NO. 2004060112

JUL 22 2003

JOHN O. FARMER

#4 MCINTYRE

10-10-21W
NW NW SE

Contr.

GRAHAM County

E 2232RB Comm.

Comp. 3/21/63

IP PMP 50 BOPD/LANS

3671-76

SMP Tops	Depth	Datum
ANH	1706	+526
HEED	3443	-1211
TOR	3463	-1231
LANS	3482	-1250
ARB	3787	-1555
TD	3794	-1562

Casing

8" 165:

3" 3789:

WAS: JONES, SHELburnE & FARMER,
#4 MCINTYRE, ARB PRODUCER
4/17/53:

NEW INFO: DP, SWB 12 BOPH, NATL:
SP 3702: PERF 3671-76:
SWB 1 1/2 GAL FREE OIL: A 1500:
SWB 3 BOPH/4 HRS: FU 750'
FLUID/12 HRS: A 3500; SWB 7 1/2
BOPH/4 HRS: POP

COOPER

+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

MAILED