

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5363  
Name: Berexco, Inc.  
Address 1: P.O. Box 723  
Address 2: P. O. Box 20380, Wichita, KS 67206  
City: Hays State: KS Zip: 67601 + \_\_\_\_\_  
Contact Person: Robert Grant  
Phone: (785) 628-6101  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
3326 Depth to Top: 3332 Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
3331 Depth to Top: 3339 Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 159-02721-00-00  
Spot Description: \_\_\_\_\_  
NW - NW SE Sec. 35 Twp. 20 S. R. 9  East  West  
2310 2282 Feet from  North /  South Line of Section  
2310 2221 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Rice  
Lease Name: Tobias Simpson Unit Well #: 6-10  
Date Well Completed: 1-6-64  
The plugging proposal was approved on: 9-9-09 (Date)  
by: Virgil Clothier (KCC District Agent's Name)  
Plugging Commenced: 9-9-09  
Plugging Completed: 9-23-09

KCC  
PKT  
OPS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	205	None
		Production	5 1/2	3384	None
Simpson	3326-39				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

9-9-09 Shoot 2 holes @ 1175, 750, 255. Run tubing to 3220 put 4 sx sand, 15 sx 60/40 pos, 4% gel, 20 sx gel, pull to 1198, spot 35 sx 60/40 pos, 4%gel and 4 sx gel. Pull to 753 spot 35 sx 60/40 pos 4% gel and 3 sx gel. Pull to 280, mix 50 sx 60/40 pos 4% gel, circulate to surface on 5 1/2. Pull tubing hook to 5 1/2, mix 65 sx 60/40 pos 4% gel, did not circulate to surface on 8 5/8.  
9-23-09 15 sx 60/40 pos, 4% gel down 5 1/2 press to 300#, held. 5 sx 60/40 pos, 4% gel down 8 5/8, press to 300#, held.

Stewart Well Service Inc

Plugging Contractor License #: 5363 31720 Name: Berexco, Inc.  
Address 1: P.O. Box 723 Address 2: P. O. Box 20380, Wichita, KS 67206  
City: Hays State: KS Zip: 67601  
Phone: (785) 628-6101

KCC PKT per CP 2/3

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Berexco, Inc. SEP 28 2009

State of Kansas County, Sedgwick, ss.

Robert Grant (Print Name)  Employee of Operator or  Operator on above-described well, CONSERVATION DIVISION WICHITA, KS

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: Robert Grant

Handwritten initials/signature