

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33629
Name: Great Plains Energy, Inc.
Address 1: PO Box 292
Address 2: 429 N. Linden
City: Wahoo State: NE Zip: 68066 +
Contact Person: Dan Blankenau
Phone: (402) 277-5336 *KCC PRT PER CP 2/3*
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 039-21081-00-00
Spot Description: _____
S/2 -NW- NW- NW Sec. 35 Twp. 4 S. R. 30 East West
450 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Decatur
Lease Name: Sauvage Family Well #: 1
Date Well Completed: 11/20/08
The plugging proposal was approved on: 11/18/08 (Date)
by: Marvin Mills (KCC District Agent's Name)
Plugging Commenced: 9:00pm 11/20/08
Plugging Completed: 7:00am 11/21/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	218'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Commenced cementing 11/20/08 @ 9:00pm. 1st plug: 25sx @ 2656', 2nd plug: 100sx @ 1920', 3rd plug: 40sx @ 267', 4th plug: 10sx @ 40', 30sx in rat hole. Total 205sx of 60-40 poz -4% gel, 1/4 # per sx flo-seal. Drilling mud was placed between plugs. Plug down 11/21/08 @ 7:00am, by SOS Cementing.

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 28 2009
CONSERVATION DIVISION
WICHITA, KS

Plugging Contractor License #: 33575 Name: WW Drilling, LLC
Address 1: 233 S. 4th St. Address 2: PO Box 307
City: WaKeeney State: KS Zip: 67672 +
Phone: (785) 743-6774
Name of Party Responsible for Plugging Fees: Great Plains Energy, Inc.
State of Nebraska County, Saunders, ss.
Daniel F. Blankenau Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: *[Handwritten Signature]*

[Handwritten Initials]