

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33629
Name: Great Plains Energy, Inc.
Address 1: PO Box 292
Address 2: 429 N. Linden
City: Wahoo State: NE Zip: 68066
Contact Person: Dan Blankenau
Phone: (402) 277-5336
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 171-20644-00-00
Spot Description: _____
SW SW NE SE Sec. 5 Twp. 17 S. R. 32 East West
1,625 Feet from North / South Line of Section
1,020 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Scott
Lease Name: Zanobia Well #: 2
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: 11/30/06 (KCC District Agent's Name)
Plugging Commenced: 4:30pm 11/30/06 & 11:00am 5/23/06
Plugging Completed: 5:30pm 11/30/06 & 1200pm 5/23/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	270'	None

RECEIVED
SEP 30 2009
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Well was temporarily abandoned on 11/30/06 w/ 50 sx @ 5100', 50sx @ 2370'. 10sx were emplaced in mouse hole and 15sx in rat hole. Total 125sx of 60-40 poz -4% gel, 1/4 # per sx flo-seal. Drilling mud was placed between plugs. Plug down 11/30/06 @ 5:30pm, by Allied Cementing. On 5/23/07 the final plugging was performed. 80sx were emplaced @ 1576', 50sx @ 1020', 40sx @ 270' and 20sx @ 60'. Total 280sx of 60-40 poz -4% gel, 1/4 # per sx flo-seal. Drilling mud was placed between plugs.

Plugging Contractor License #: 30606 31627 Name: Whitetail Crude Inc
Murfin Drilling Company, Inc.
Address 1: 250 North Water St., Ste 300 Address 2: _____
City: Wichita State: KS Zip: 67202
Phone: (316) 267-3241
Name of Party Responsible for Plugging Fees: Great Plains Energy, Inc.

State of Nebraska County, Saunders, ss.
Daniel F. Blankenau Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: D.F. Blankenau

KCC PICT
POT CP2/3

POT