

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Tri United, Inc
Address: 950 270th Ave Hays, Ks 67601
Phone: (785) 628-3670 Operator License #: 03194
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 8-27-09 (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No

API Number: 15-051-19094-00-00
Lease Name: Gross
Well Number: 2X
Spot Location (QQQQ): NE-SE-SE
990' Feet from North / South Section Line
330' Feet from East / West Section Line
Sec. 25 Twp. 13 S. R. 18 East West
County: Ellis
Date Well Completed: 6-9-64
Plugging Commenced: 9-2-09
Plugging Completed: 9-02-09

Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3522 Bottom: 3528 T.D. _____
LKC Depth to Top: 3495 Bottom: 3500 T.D. _____
LKC Depth to Top: 3456 Bottom: 3460 T.D. _____
LKC 3430 3432

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>LKC</u>	<u>oil & Wtr</u>	<u>Surf</u>	<u>226'</u>	<u>8 5/8</u>	<u>226'</u>	<u>none 150sks cement</u>
		<u>Surf</u>	<u>3675'</u>	<u>4 1/2</u>	<u>3675'</u>	<u>none 150sks cement</u>


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tubing to 1134' Allied pumped down tubing with 60sks 60/40 poz 4% gel
Pulled tubing to 600' Perf thru tubing, Allied pumped thru tubing 25sks
then another 110sks mixed with 300#hulls circulated up 4 1/2, pulled tubing
perf at 175' tye on to 4 1/2 casing pumped 55sks with 50#hulls 150# pressure
Shut in Tye to 8-5/8 pumped 35sks cement 300# pressure, Shut in.

Name of Plugging Contractor: Tri United, Inc / Allied Cementing License #: 03194
Address: 950 270th Ave Hays, Ks 67601
Name of Party Responsible for Plugging Fees: Tri United, Inc
State of Kansas County, Ellis ss.

RECEIVED
OCT 23 2009
KCC WICHITA

Eugene Leiker (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Eugene E Leiker President
(Address) 950 270th Ave Hays, Ks 67601

SUBSCRIBED and SWORN TO before me this 21st day of October, 2009
Keith Bunger Notary Public My Commission Expires: 2/26/13

ALLIED CEMENTING CO., LLC. 038537

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

API # 15-051-19094

SERVICE POINT: OGP

DATE <u>9-2-09</u>	SEC. <u>25</u>	TWP. <u>17</u>	RANGE <u>18</u>	CALLED OUT	ON LOCATION	JOB START <u>11:30 A.M.</u>	JOB FINISH <u>12:30 P.M.</u>
LEASE <u>Gross</u>	WELL# <u>2X</u>	LOCATION <u>NE-SE-SE T-70 State Rd</u>			COUNTY <u>Ellis</u>	STATE <u>KS</u>	
(OLD OR NEW (Circle one)) <u>NESESE</u> <u>1/2 N 1 W 1/4 N W into</u>							

CONTRACTOR Co Tools
 TYPE OF JOB PTA
 HOLE SIZE _____ T.D. 3676
 CASING SIZE 4 1/2 DEPTH 3675
 TUBING SIZE 2 3/8 DEPTH 1334
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER _____
 CEMENT AMOUNT ORDERED 285 60% 42 C.I.
300 4 1/2 1/2
 COMMON @ _____
 POZMIX @ _____
 GEL @ _____
 CHLORIDE @ _____
 ASC @ _____
 @ _____
 @ _____
 @ _____
 @ _____
 @ _____
 @ _____
 @ _____
 HANDLING @ _____
 MILEAGE _____

EQUIPMENT

PUMP TRUCK CEMENTER Shane
 # 181 HELPER Galen
 BULK TRUCK _____
 # 344 DRIVER Randy
 BULK TRUCK _____
 # _____ DRIVER _____

REMARKS:

Tubin @ 1334 - Mixed - 60 sts
Pulled 2 3/8 tubin up to
600' to Circulate Cement
Circulated Cement with 135 sts
with 300 # hells. Came out
of hole set swage ON Mixed
55 sts with 50 # hells shot in
@ 150 ps Tied on backside
Mixed 35 sts and shot in @ 275 ps

RECEIVED
 TOTAL
 OCT 23 2009
 SERVICE
 KCC WICHITA

CHARGE TO: Tri United Inc.
 STREET _____
 CITY _____ STATE _____ ZIP _____

DEPTH OF JOB _____
 PUMP TRUCK CHARGE _____
 EXTRA FOOTAGE @ _____
 MILEAGE @ _____
 MANIFOLD @ _____
 @ _____
 @ _____

TOTAL _____

PAT STAAB STATE plugger
witnessed entire plug.

PLUG & FLOAT EQUIPMENT

@ _____
 @ _____
 @ _____
 @ _____
 @ _____

TOTAL _____

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

SALES TAX (If Any) _____
 TOTAL CHARGES _____
 DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME Eugene E Carter
 SIGNATURE Eugene E Carter