

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-9-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5447  
Name: Oxy USA, Inc.  
Address 1: PO Box 2528  
Address 2: \_\_\_\_\_  
City: Liberal State: KS Zip: 67905  
Contact Person: Kenny Andrews  
Phone: (620) 629 4232  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Morrow Depth to Top: 4845' Bottom: 4894' T.D. 5000'  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

API No. 15 - 129-20295-0000  
Spot Description: SE 1/4 NE NE  
SE 1/4 NE NE Sec. 32 Twp. 34 S. R. 41 East  West   
660 Feet from  North /  South Line of Section  
70 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Morton  
Lease Name: WMSIA Well #: 901  
Date Well Completed: 12-5-76  
The plugging proposal was approved on: 9-17-09 (Date)  
by: Ken Jehlik (KCC District Agent's Name)  
Plugging Commenced: 9-21-09  
Plugging Completed: 9-22-09

RECEIVED

OCT 26 2009

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records |         | Casing Record (Strikes, Conductor & Production) |       |              |            |
|---------------------------|---------|---|-------|--------------|------------|
| Formation                 | Content | Casing  | Size  | Bottom Depth | Pulled Out |
|                           |         |   | 8 5/8 | 1437         |            |
|                           |         |   | 5 1/2 | 4999         | 1738       |
|                           |         |   |       |              |            |
|                           |         |   |       |              |            |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

HLS set CIBP + 2 sx cmt. from 4800' to 4785'. Shot & pulled 5 1/2 to 1500. Circ. hole & mixed 50 sx plug 1500 to 1350 40 sx plug 500 to 380 10 sx plug 40 to 0 Capped 8 5/8 3 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent + Horton Plugging Inc.  
Address 1: Rt 1 Box 49 BA Address 2: \_\_\_\_\_  
City: Tyrone State: OK Zip: 73951 + 9731  
Phone: (580) 854 6515  
Name of Party Responsible for Plugging Fee: Oxy USA Inc. 1701 N. Kansas PO Box 2528 Liberal, KS. 67905  
State of Kansas County: Sevier, ss.  
Kenny Andrews (Print Name)  Employee of Operator or  Operator on above-described well,

being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Kenny Andrews

PA